NEW WALL - STUD & GYP. BD.	
EXISTING WALL OR FLOOR	
DEMO AND REMOVE	
EXISTING DOOR	DEMO E.T.R.
NEW DOOR	

BUILDING AREA = 16,509 SF

NOTES:
1. PROVIDE SPRINKLER SYSTEM
2. REFURBISH EXISTING WINDOWS AND PROVIDE NEW INTERIOR STORM WINDOWS
3. PROVIDE NEW ROOFTOP HVAC SYSTEM AND DUCTS.

TYPICAL FINISHES
FLOOR: NEW VCT
CEILING: NEW 1X1 ACT
WALLS: PAINT EXG CMU

IN CLASSROOM BATHROOMS:
GRAB BAR HEIGHT = 20"
DISPENSER HEIGHT = 14"

1 1ST FLOOR - NEW
1/8" = 1'-0"

LICENSED ARCHITECT DAVID LLOYD NO. 936 STATE OF MAINE
Date: 01/24/18

Prepared For: Children's Odyssey

Consultant:

Architect: ARCHETYPE architects
48 Union Wharf Portland, Maine 04101
(207) 772-6022 ARCHETYPE@ARCHETYPEPA.COM

Project: CHILDREN'S ODYSSEY
19 LIBBY STREET
PORTLAND, ME 04103

Revisions:
1 | Date 1 | Revision 1

Scale: 1/8" = 1'-0"

Date: OCT, 2016

FLOOR PLAN

A1.01