

8 NEW 40" X 62" WINDOWS (DOUBLE HUNG LOWE)

① NEW 32" X 20" CRANK-OUT WINDOW LOW-E TO BE INSTALLED GICE AND WATER SEALED) WHITE VINYL TO MATCH EXISTING VINYL ON THE 1ST FLOOR TO BE INSTALLED BY OWNER

TYPAR ON EXTERIOR WALLS (STAPLED)

3 TAB BLACK SHINGLES TO BE INSTALLED W/6' X 32' ICE/WATER AND 8" PREP EDGE AROUND EDGES OF ROOF

EXTERIOR WALL SHEATHING TO BE 1/2" CDX PLYWOOD

ROOF SHEATHING TO BE 5/8" CDX

TRUSSES VENTED (BOTH ENDS)

RIDGE VENT 26' OVER SINGLES

VENTED VINYL SOFFETT 32' FRONT AND BACK (EAST) AND (WEST)

DEM'D MATERIALS CONSIST OF ORIGINAL SHINGLES (1 LAYER) AND INTERIOR SHEET ROCK PLUS ② DOUBLE HUNG WINDOWS OF WOOD AND 352 CUBIC FEET OF INSULATION.

ESTIMATED COST TO COMPLETION \$12,000⁰⁰

NOT INCLUDING PERMIT FEES. X Nataly y Jellal
OWNER