Reviewed for Code Compliance
Approved Inspection
Approved with Conditions
Date: 08/29/16

2 FOUNDATION PLAN - ADDITION

SCALE: 1/2"= 1'-0"
NOTE: NO FINISHED FLOOR AREA
COORDINATE STRUCTURE WITH LVL SIZING

DECK CONSTRUCTION:

5/4"X6" AZEK DECKING OVER PRESSURE TREATED 2X10 JOISTS @ 16" O.C. R-30 FIBERGLASS W/CONT. 2" T&G RIGID INSULATION UNDER JOIST TAPE SEAMS - GRADE VARIES

2X10 PRESSURE TREATED LEDGER FASTENED TO RIM W/5/8"X6" LAG ANCHORS STAGGERED @ 24" O.C.

(2) 2X10 PRESSURE TREATED BEAM (FLUSH) SECURED TO CONCRETE WITH SIMPSON BRACKET. ALTERNATE IS TO POST W/6X6 PT FROM CONCRETE TO BEAM USE SIMPSON FOR CONNECTIONS & BACKFILL TO FINISH GRADE

FASTEN CONT. 1X SKIRT BOARD & BURY

2" RIGID INSUL MIN. DEPTH 2' BELOW GRADE - FACE WITH PT. PLYWOOD

BIGFOOT BF28 OR EQUAL 'FOOTING' AT ALL SONOTUBES

A FOUNDATION SECTION AT DECK

SCALE - ½" = 1'-0"