



- NOTES:**
1. PROVIDE DIN RAIL MOUNTED SIGNAL SPLITTER IN NEAR 4X SS BOX, MOUNT IN TUNNEL AREA ADJACENT TO EXISTING FI-730.
 2. PROVIDE DIN RAIL MOUNTED SIGNAL PANEL (COP).
 3. PROVIDE 3-WAY MOTORIZED BALL VALVES (TYPICAL OF 2) ON EACH BYPASS ANALYZER SAMPLE LINE.

PORTLAND WATER DISTRICT
 PORTLAND, MAINE
 EAST END WWTF DISINFECTION AND
 DECHLORINATION SYSTEMS UPGRADE
 CHLORINE CONTACT



DRAWN BY SJM
 CHECKED BY SLH/PFB
 DATE 2-18-05
 APPROVED BY PFB
 DATE 2-18-05
 BOOK NO. -
 PROJECT NO. 10301C
 SCALE AS NOTED

NO	REVISIONS	APP'D	DATE	PROGRESS PRINTS
1				ISSUED FOR REVIEW: 12-15-04
2				ISSUED FOR BIDDING: 2-18-05
				VALVE LOCATION: FF 58
				LAST WORKED ON:
				FILENAME: