Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 12/08/14

PLUMBING FIXTURE SCHEDULE

TAG	DESCRIPTION	BRANCH SIZES									GENERAL NOTES
		TW	NCW	NHW	CW	HW	ACID-VENT	ACID-WASTE	VENT	WASTE	
P-1	LAB SINK WITH DRAIN BOARD (SINGLE BAY)	-----	1/2"	1/2"	-----	-----	1 1/2"	1 1/2"	-----	-----	(SINK, FAUCET & GAS COCK PROVIDED BY DIVISION 12)
NB-1	NEUTRALIZATION BASIN -15 GALLON	-----	-----	-----	-----	-----	2"	3"	-----	3"	ORION, MODEL ORT 0015
NB-2	NEUTRALIZATION BASIN POINT OF USE - 5 GALLON	-----	-----	-----	-----	-----	1 1/2"	2"	-----	2"	ORION, STYLE 9
NB-3	NEUTRALIZATION BASIN POINT OF USE - 5 GALLON	-----	-----	-----	-----	-----	1 1/2"	2"	-----	2"	ORION, STYLE 9
DW	DISH WASHER HOOK-UP	-----	-----	-----	-----	1/2'	-----	-----	1 1/2"	1 1/2"	
EW-1	EMERGENCY EYEWASH/SHOWER	1 1/2"	-----	-----	-----	-----	-----	-----	-----	-----	
EW-2	EMERGENCY EYEWASH/ DECK MOUNTED	3/4"	-----	-----	-----	-----	-----	-----	-----	-----	
FD	FLOOR DRAIN	-----	-----	-----	-----	-----	-----	-----	1 1/2"	3"	PROVIDE TRAP PRIMER

F6 SCHEDULE ~ PLUMBING
NONE

D1 DETAIL ~ FLOOR DRAIN
NONE

D3 DETAIL ~ NCW & NHW BACKFLOW PREVENTER PIPING
NONE

A1 DETAIL ~ MIXING VALVE PIPING
NONE

A3 DETAIL ~ TRAP PRIMER PIPING
NONE

A6 DETAIL ~ EMERGENCY EYEWASH
NONE

PDT ARCHITECTS
49 DARTMOUTH STREET
PORTLAND, MAINE 04101
207-775-1059
www.pdtarchs.com

COPYRIGHT 2014
PDT Architects
Reuse or reproduction of the contents of this document is not permitted without written permission of PDT Architects.

Allied Engineering
Structural Mechanical Electrical Commissioning
160 Veranda Street
Portland, Maine 04103
T: 207.221.2260
F: 207.221.2266
Web: www.allied-eng.com

allied Project No: 14-024
CAD File: 14024_P

Minor Interior Renovations at 196 Allen Avenue for Casco Bay High School 196 Allen Avenue, Portland Maine

NORTH

STATE OF MAINE ANTHONY S. DAVIS No. 8834 LICENSED PROFESSIONAL ENGINEER

JOB NO. 14036

DRWN. CHK

SCALE: As Indicated

ISSUE STATUS CONSTRUCTION
ISSUE DATE APRIL 18, 2014

TITLE PLUMBING SCHEDULES, DETAILS & NOTES

SHEET PL-500

N:\Projects\2014\14024 ~ CBHS Chemistry Room and Assembly Space Renovations\00 Drawing Files\14024_P.dwg Apr 18, 2014 ~ 9:13am