Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 12/08/14

CEILING GENERAL NOTES

1. Ceiling plans do not show every fixture or component. Refer to electrical, plumbing, mechanical and structural drawings for extent of all ceiling penetrations and installations and coordinate prior to installation.
2. Center grid layout in all rooms unless noted otherwise.
3. All components mounted in or below a suspended acoustic ceiling shall be centered in the ceiling tile or in the 2x2 portion of tegular tiles. This shall include, but not be limited to, light fixtures, diffusers, speakers, and sprinkler heads.
4. Prior to the installation of ceilings, allow for an above-ceiling inspection of components that will not be visible when the ceilings have been installed.
5. Coordinate new ceiling grid size and layout with the size and quantity of Salvaged ceiling tile.

2 THIRD FLOOR CEILING PLAN
1/8" = 1'-0"

CEILING LEGEND

TYPE / HEIGHT	CEILING TYPE KEY AND HEIGHT
	C1 - GWB CEILING ON METAL FRAMING
	C2 - SALVAGED 2 X 4 ACOUSTICAL CEILING TILE. NEW GRID
	C3 - NEW 2 X 4 ACOUSTICAL CEILING TILE AND GRID
	EXISTING CEILING TO REMAIN. REPAIR AND REPLACE GRID AND TILE AS NEEDED.
	NOT IN SCOPE
	SUPPLY AIR GRILLE
	RETURN AIR GRILLE
	EXHAUST AIR GRILLE
	2 X 4 LIGHT FIXTURE

4 SECOND FLOOR CEILING DEMO PLAN
1/8" = 1'-0"

3 TYPICAL CEILING DETAILS
1 1/2" = 1'-0"

0' 4' 8' 16' 32'

PDT ARCHITECTS
49 DARTMOUTH STREET
PORTLAND, MAINE 04101
207-775-1059
www.pdtarchs.com

COPYRIGHT 2014
PDT Architects
Reuse or reproduction of the contents of this document is not permitted without written permission of PDT Architects.

Minor Interior Renovations at 196 Allen Avenue for
CASCO BAY HIGH SCHOOL
196 Allen Avenue, Portland Maine

NORTH

REGISTERED ARCHITECT
LYNDON
No. 1142
STATE OF MAINE

JOB NO.
14036

DRWN. CHK
Checker

SCALE:
As indicated

ISSUE STATUS
CONSTRUCTION

ISSUE DATE
APRIL 18, 2014

TITLE
REFLECTED CEILING PLAN

SHEET
A103