Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 12/08/14

2 THIRD FLOOR FINISH PLAN
1/8" = 1'-0"

ROOM FINISH SCHEDULE

NUMBER	ROOM NAME	FLOOR	BASE MATL	WALLS N	WALLS S	WALLS E	WALLS W	ROOM NO.	NOTES
A301a	CORRIDOR	EXISTING	EXISTING	PTD	PTD	PTD	PTD	A301a	ALTERNATE #1. MATCH AND PATCH EXISTING CPT AS REQUIRED
A301b	CORRIDOR	EXISTING	EXISTING	PTD	PTD	PTD	PTD	A301b	MATCH AND PATCH EXISTING CPT AS REQUIRED
A301c	CORRIDOR	EXISTING	EXISTING	PTD	PTD	PTD	PTD	A301c	ALTERNATE #2. SEE 2/A102 FOR DEMARKATION OF NEW AND EXISTING CARPET
A301d	OPEN PLAN EDUCATIONAL	CPT-1	MATCH EXISTING	PTD	PTD	PTD	PTD	A301d	ALTERNATE #2. SEE 2/A102 FOR DEMARKATION OF NEW AND EXISTING CARPET
A302	OPEN PLAN EDUCATIONAL	CPT-1	MATCH EXISTING	PTD	PTD	PTD	PTD	A302	ALTERNATE #1
A303	SCIENCE CLASSROOM	VCT	RB	PTD	PTD	PTD/WPTD	PTD	A303	
A303a	PREP ROOM	VCT	RB	PTD	PTD	PTD	PTD	A303a	

FINISH ABBREVIATIONS:

PTD - PAINT
Sherwin Williams – allow for up to 5 colors TBD

PLY - PLYWOOD

RB - WALL BASE
Johnsonite 4"h x 1/8" Traditional base – Type [TP].

CPT - CARPET

CPT-1 Tandus/Collins & Aikman 'Explorer' 'STARLIGHT' (25004)

VCT - VINYL COMPOSITION TILE
Mannington 'Essentials', Armstrong Excelon' (allow for up to 6 colors TBD)

WPTD- WHITEBOARD PAINT
Idea Paint White Finish

FINISH GENERAL NOTES:

1. SEE ALTERNATES.
2. HM FRAMES TO BE PAINTED.
3. CONTRACTOR TO PERFORM ALKALINITY AND ADHESION TESTS (ASTM F1869 & 2170) RECOMMENDED BY FLOORING MANUFACTURERFOR EACH FLOORING TYPE. PROCEED WITH FLOORING TYPE ONLY AFTER SUBSTRATES PASS TESTING. VERIFY RESULTS WITH FLOORING MANUFACTURER.
4. ALL PAINT TRANSITIONS SHALL BE AT INSIDE AND OUTSIDE CORNERS UNLESS OTHERWISE NOTED.
5. HOLLOW METAL DOORS AND FRAMES: PAINT COLOR TBD

FINISH LEGEND

CARPET (CPT-1)
VINYL COMPOSITION TILE (VCT-)
NOT IN SCOPE
NO FLOORING CHANGE

0' 4' 8' 16' 32'

REV.	DESCRIPTION	DATE
1	REVISION #1	APRIL 25, 2014
0	ISSUED FOR CONSTRUCTION	APRIL 18, 2014

PDT ARCHITECTS
49 DARTMOUTH STREET
PORTLAND, MAINE 04101
207-775-1059
www.pdtarchs.com

COPYRIGHT 2014
PDT Architects
Reuse or reproduction of the contents of this document is not permitted without written permission of PDT Architects.

Minor Interior Renovations at 196 Allen Avenue for
CASCO BAY HIGH SCHOOL
196 Allen Avenue, Portland Maine

REGISTERED ARCHITECT
LYNDON A. KIRK
No. 1342
STATE OF MAINE

JOB NO.
14036

DRWN. CHK
AHC

SCALE:
As indicated

ISSUE STATUS
CONSTRUCTION

ISSUE DATE
APRIL 18, 2014

TITLE
FINISH SCHEDULE AND PLANS

SHEET
A601