Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 12/08/14

DOOR AND FRAME SCHEDULE													
DOOR NUMBER	DOOR TYPE	HEIGHT	WIDTH	THICKNESS	DOOR MATERIAL	GLAZING	RATING	FRAME TYPE	FRAME MATERIAL	HEAD	JAMB	DOOR NUMBER	COMMENTS
A301a	RELOCATED EXISTING (TYPE A3)	7' - 0"	3' - 0"	1 3/4"	RELOCATED EXISTING	HG	--	RELOCATED EXISTING (TYPE 1A)	RELOCATED EXISTING	C3/A600	C3/A600	A301a	SMOKE RATED, CLOSER. RELOCATED DOOR FROM DEMO NOTE #02.D3 ON 1/AD102
A301b	RELOCATED EXISTING (TYPE A3)	7' - 0"	3' - 0"	1 3/4"	RELOCATED EXISTING	HG	--	RELOCATED EXISTING (TYPE 1A)	HM	C3/A600	C3/A600	A301b	SMOKE RATED, CLOSER. RELOCATED DOOR FROM DEMO NOTE #02.D2 ON 1/AD102
A303	A4	7' - 0"	3' - 0"	1 3/4"	RELOCATED EXISTING	NG	20 MINS.	RELOCATED EXISTING (TYPE 1A)	HM	C3/A600	C3/A600	A303	SMOKE RATED, CLOSER. TEMPERED
A303a	A1	7' - 0"	3' - 0"	1 3/4"	WD	--	20 MINS.	1A	HM	C3/A600	C3/A600	A303a	SMOKE RATED, CLOSER.
A303b	A1	7' - 0"	3' - 0"	1 3/4"	WD	--	--	1A	HM	C3/A600	C3/A600	A303b	SMOKE RATED, CLOSER
A303c	A4	7' - 0"	3' - 0"	1 3/4"	WD	NG	20 MINS.	1A	HM	C3/A600	C3/A600	A303c	SMOKE RATED, CLOSER. TEMPERED

DOOR & WINDOW GENERAL NOTES

1. Solidly pack all interior hollow metal frames with mineral-fiber insulation.
2. Refer to Specifications for locations of Tempered, Wired, or Insulating Glass, unless noted otherwise.
3. Unless noted otherwise, the location of doorframes shall be:
   - 4" from adjacent wall to the hinge side in metal stud partitions.
   - Maintain a **clear** dimension of 1'-6" from all adjacent construction to the latch (pull) side of the door.
   - Maintain other **clear** dimensions in accordance with the latest version of the ADA Accessibility Guidelines (ADAAG).

FURNITURE, EQUIPMENT AND FINISHES GENERAL NOTES:

OWNER PROVIDED AND INSTALLED ITEMS INCLUDE:
SIGNAGE
TACK BOARDS (TB)
MARKER BOARDS (MB)

GC PROVIDED/ GC INSTALLED ITEMS INCLUDE
(NOT LIMITED TO):
FIRE EXTINGUISHERS (FE)

1 DOOR FRAME TYPES
3/8" = 1'-0"

2 DOOR TYPES
3/8" = 1'-0"

C3 HM FRAME DETAILS @ GWB
1 1/2" = 1'-0"

Window Schedule					
TYPE	COUNT	HEIGHT	WIDTH	HEAD HEIGHT	NOTES
W1	1	7' - 0"	3' - 0"	7' - 0"	
Grand total: 1					

3 WINDOW TYPES
3/8" = 1'-0"

WINDOW HM HEAD DETAIL

WINDOW HM JAMB DETAIL

B4 WINDOW HEAD AND JAMB
1 1/2" = 1'-0"

REV.	DESCRIPTION	DATE
1	REVISION #1	APRIL 25, 2014
0	ISSUED FOR CONSTRUCTION	APRIL 18, 2014

PDT ARCHITECTS
49 DARTMOUTH STREET
PORTLAND, MAINE 04101
207-775-1059
www.pdtarchs.com

COPYRIGHT 2014
PDT Architects
Reuse or reproduction of the contents of this document is not permitted without written permission of PDT Architects.

Minor Interior Renovations at 196 Allen Avenue for
CASCO BAY HIGH SCHOOL
196 Allen Avenue, Portland Maine

REGISTERED ARCHITECT
LYNDON
CLARK
No. 1142
STATE OF MAINE

JOB NO.
14036

DRWN. CHK
AHC

SCALE:
As indicated

ISSUE STATUS
CONSTRUCTION

ISSUE DATE
APRIL 18, 2014

TITLE
SCHEDULES

SHEET
A600