Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 06/19/17

PATHS – Fire Alarm Upgrade

Remove existing FACP and old generation City boxes.

Replace with new addressable FACP and wireless AES city box.

ADD NAC devices throughout to bring up to code.

Add monitor modules to existing pull stations to make addressable.

Add new addressable pull stations as indicated on prints.

Add new heat detectors as indicated on prints.

Add new smoke detectors as indicated on prints.

Add new duct smoke detectors with reset test switch as indicated on prints.

Add monitor modules for existing Sprinkler system switches to make fully addressable.

Adding 3 power extenders to cover voltage drop throughout building.

Remove existing devices not used on new system.