

SECTION 09680 - CARPETING

PART I - GENERAL

1.01 DESCRIPTION

- A. The extent of carpet installation is shown on schedules.
- B. Carpeting will be furnished and installed by Walgreens. This section describes the quality of related work to be provided by the General Contractor.

1.02 QUALITY ASSURANCE

- A. Flame/Smoke Resistance Standards: Walgreens supplied materials comply with the following:
 - 1. Pill Test: For flammability, complies with ASTM D 2859 or DOC FF-1-70.
 - 2. Floor Radiant Test Panel: Critical Radiant Flux (CRF) not less than 0.45 watts/sq. cm. per ASTM E 648, Class I.
 - 3. Smoke Density Test: Complies with ASTM E 662, less than 450.

PART II - PRODUCTS

2.01 CARPET (provided by Walgreens)

- A. Manufacturer: Interface Carpet Tile with Super Cushion back.
 - 1. Pattern: Urban Grid.
 - 2. Color: Taupe #5423.
 - 3. Size: 18" x 18".

2.02 ADHESIVE

- A. Re: Source Grid-Set Green Glue 2000, pressure sensitive adhesive on all areas except stairs.

PART III - EXECUTION

3.01 INSTALLATION (by Walgreens)

3.02 PRE-INSTALLATION REQUIREMENTS (by General Contractor)

- A. Clear away debris and scrape up cementitious deposits from surfaces to receive carpet.
- B. Protect installed carpet from damage and soilage during remaining construction.
- C. Ensure that carpet will be without deterioration or damage at time of acceptance by Walgreens.

END OF SECTION

