

SECTION 10190 - TOILET PARTITIONS AND ACCESSORIES

PART I - GENERAL

1.01 DESCRIPTION

- A. The extent of toilet partitions and accessories is shown on drawings.
- B. Provide floor mounted, headrail braced toilets partitions and wall hung screens.
- C. Types of toilet accessories include:
  - Paper towel dispensers
  - Waste receptacles
  - Feminine napkin disposal
  - Toilet tissue dispenser (furnished and installed by Walgreens)
  - Grab bars
  - Mirrors
  - Diaper Changing Station

1.02 QUALITY ASSURANCE

- A. Coordination: Furnish inserts and blocking to support toilet partitions and accessories.
- B. All toilet accessories shall be from the same manufacturer except Walgreens furnished.
- C. Hardware and door openings shall be fabricated to comply with requirements of the Americans with Disabilities Act, and ANSI A 117-1. (Latest Edition).

PART II - PRODUCTS

2.01 TOILET PARTITIONS AND SCREENS

- A. Manufacturer: Toilet Partition: headrail braced with baked enamel finish.
- B. Acceptable Manufacturers:
  - Accurate Partitions Corp., floor Anchored/Overhead Braced series, power coated steel color #917 Adobe.
  - American Sanitary Partition Corp., headrail braced "Full Flush Type", baked enamel color; #34 San Tan..
  - AMPCO Products, Inc. Overhead braced toilet compartment, baked enamel color #958-58 Beige.
  - Flush-Metal Partition Corp., headrail braced "Flushite" series, color #35 Beige.
  - General Partitions Mfg. Corp., headrail braced "Series 40, color #SN-336 Sand.
  - Global Steel products Corp., "Floor Anchored/Overhead Braced" series, color #2115 Khaki.
  - Hadrian Manufacturing, Inc., headrail braced, floor mounted system, color #585 Sahara.
  - Knickerbocker Partition Corp., headrail braced "Metropolitan" series, color; Sand #5123.
- C. Urinal Screens: By same manufacturer and in same color as toilet partitions. Size; 18" x 42".
- D. Hardware: Manufacturers standard heavy duty, chrome plated; self-closing hinges, lever handle latch with emergency access, door pull, doorkeeper with bumpers, coat hook with bumper and stainless steel pilaster shoes.
- E. Headrail: Manufacturers standard anti-grip style.

2.02 TOILET PARTITION/SCREEN MATERIALS

- A. Sheets for baked enamel finish: ; ASTM A 591, Class C, galvanized-bonderized.
- Pilasters: 20 gauge  
Panels and screens: 20 gauge  
Doors: 22 gauge
- B. Partition Core Materials: 1" finished thickness with sound-deadening honeycomb core.
- Pilasters shall be 1-1/4" thick.
- C. Pressure laminate seamless face sheets to core material and steel edges with continuous interlocking strip. Weld edges and corners and grind smooth.

2.03 TOILET ACCESSORIES

- A. Manufacturer: Bobrick unless noted otherwise.
- Recessed roll paper towel dispenser/waste receptacle: Bradley #2277.  
Feminine napkin disposal: #B-270  
Toilet tissue dispenser: North American Paper #WA56T, double jumbo (by Walgreens).  
Grab Bars: (1) B-6806 x 36 and (1) B-6806 x 42.  
Mirror: B-165-1836.  
Employee Room surface mounted roll paper towel dispenser: B-2860
- B. Acceptable Alternate Manufacturers: Bradley Corporation.

2.04 TOILET ACCESSORY MATERIALS

- A. Stainless Steel: AISI Type 302/304, with polished no. 4 finish, 22 gauge minimum.
- B. Mirror Glass: FS DD-G-451, Type I, Class 1, Quality q2, 1/4" thick with silver coating, copper protective coating and non-metallic paint coating.

2.05 DIAPER CHANGING STATION

- A. Baby Changing Station: Provide Koala Kare Products (or equal) wall mounted horizontal design, molded FDA approved HDPE, 300 lb. capacity, molded braille instructions;
1. Hinges: reinforced, full length steel on steel.
  2. Mounting Supports: multiple 11 ga. steel.
  3. Operation: pneumatic gas spring mechanism.
  4. Color: beige.
  5. Provide and location identifying signage as required by local ordinances.
  6. Provide "Microban Technology" anti-microbial product protection

3.01 INSTALLATION

- A. Install toilet partitions and accessories plumb, level and securely anchored. Mount accessories using concealed vandal proof fasteners, at heights as shown on drawings.

3.02 ADJUST AND CLEAN

- A. Adjust hardware and accessories for proper operation.
- B. Toilet partition doors to swing open approx. 30 degrees when unlatched.
- C. Clean toilet partition surfaces and accessories. Replace all defective or damaged items.

END OF SECTION

