

SECTION 10522 - FIRE PROTECTION SPECIALTIES

PART I - GENERAL

1.01 DESCRIPTION

- A. Wall mounted fire extinguishers and accessories.
- B. Recessed Key Lock Boxes (provide only when required by local codes/officials).

1.02 QUALITY ASSURANCE

- A. Comply with applicable requirements of NFPA 10 and ADA Accessibility Guidelines.
- B. Provide UL listed and FM approved fire extinguishers which bear the UL listing mark for the type, rating and class of fire extinguisher indicated.
- C. Obtain products from one manufacturer.

PART II - PRODUCTS

2.01 FIRE EXTINGUISHERS

- A. Multi-Purpose Dry Chemical Type: UL rated 4A:60B:C. or as required by local authority.
- B. Finish: Manufactures standard factory applied RED.
- C. Provide not less than six (6) fire extinguishers (more if required by local authorities).
- D. Manufacturers: JL Industries Inc.
Larsen's Manufacturing Co.
Potter-Roemer

2.02 ACCESSORIES

- A. Mounting Brackets: manufacturers standard for the fire extinguisher furnished.
- B. Signs: provide signs identifying the locations of fire extinguishers as required by local authorities.

2.03 KEY KNOX BOX (Provide only when required by local codes/officials)

- A. Recessed Knox Box #3200-R, with UL listed alarm tamper switch, dark bronze finish.

PART III - EXECUTION

3.01 INSPECTION

- A. Verify servicing, charging and tagging of all fire extinguishers.

3.02 INSTALLATION

- A. Install fire extinguishers and identifying signs in compliance with local authorities and ADA guidelines.
- B. Provide blocking and anchoring devised capable of supporting specified fire extinguishers.

- C. Recessed Knox Box shall be installed 6'-0" above top of foundation, near main entry as directed by local fire officials.

END OF SECTION