

SECTION 12484 - FLOOR MATS AND FRAMES

PART I - GENERAL

1.01 DESCRIPTION

- A. The extent of floor mat installation (surface and recessed) is shown on Walgreens Fixture Plan.
- B. Floor mats will be furnished and installed by Walgreens. This section describes the quality of related work to be provided by the General Contractor.
- C. The General Contractor shall be responsible for installing the vestibule recess and floor drain in stores designated to receive an entry vestibule.

1.02 QUALITY ASSURANCE

- A. Flame/Smoke Resistance Standards: Walgreens supplied materials comply with the following:
  - 1. Pill Test (entrance grid): For flammability, complies with ASTM D 2859, < 1 inch.
- B. Surfaces designated to receive floor mats shall be constructed in accordance with the manufacturer's instructions.

PART II - PRODUCTS

2.01 FLOOR MAT (provided by Walgreens)

- A. Manufacturer: Space-Links®, Inc.
- B. Entrance Grid: Recessed or surface mounted, with aluminum frame.
  - 1. Style: Ultra-Links Entryway Flooring System™.
  - 2. Type: Entrance grid.
  - 3. Size: 4-ft. x 4-ft.
  - 4. Thickness: 15/32 inch
  - 5. Color: Gray
- C. Carpet Tiles:
  - 1. Style: Dreadnought.
  - 2. Color: Anthracite.
  - 3. Adhesive: TacFast backing.
  - 4. Edging: Black rubber.

PART III - EXECUTION

3.01 INSTALLATION (by Walgreens)

3.02 PRE-INSTALLATION REQUIREMENTS (by General Contractor)

- A. At recessed installations, install floor drain and prepare recess in accordance with Walgreens Criteria details. Slope recess to drain located at center of recessed area.
- B. Clear away debris and scrape up cementitious; deposits from surfaces to receive floor mats.
- C. Protect installed floor mats from damage during remaining construction.
- D. Ensure that floor mat will be undamaged at time of acceptance by Walgreens.
- E. Surface mounted floor mats shall be installed on top of resilient flooring.

END OF SECTION