

COMMENTS

7/17/00 - Pre-Gen by Plans - General Setbacks / Ladder enclosures / Separate permit for future deck, etc. (E)

7/19/00 Self Inspect OK (FC)

4/10/02 - direct access from house - gate non compliant 6/19 of ~~structural product~~

Plumbing Pass from deck OK JB

N.O.V. Sent 4/11/02 (E)

5/21/02 Owner Made Some progress - Still Needs higher Gate at pool TX till - 6/4/02 (E)

6/19/02 New Gate installed at Pool Latch 54" - Spring - self Latching JB

344-G-29
000754

Inspection Record

Type	Date
Foundation: _____	_____
Framing: _____	_____
Plumbing: _____	_____
Final: _____	_____
Other: _____	_____

ELECTRICAL PERMIT

City of Portland, Me.



K

To the Chief Electrical Inspector, Portland Maine:
 The undersigned hereby applies for a permit to make electrical installations in accordance with the laws of Maine, the City of Portland Electrical Ordinance, National Electrical Code and the following specifications:

Date Sept 9 1999
 Permit # _____
 CBL# 344-6-029

SITE LOCATION: 27 Cypress Street

OWNER Edgar Bilalawa **TENANT** _____

								TOTAL EACH FEE		
OUTLETS	Receptacles	30	Switches	10	Smoke Detectors	5		.20	9.00	
FIXTURES	incandescent	10	fluorescent		Strips			.20	2.00	
SERVICES	Overhead		Underground		TTL AMPS	<800		15.00		
	Overhead		Underground			>800		25.00		
Temporary Service	Overhead		Underground		TTL AMPS			25.00		
								25.00		
METERS	(number of)							1.00		
MOTORS	(number of)							2.00		
RESID/COM	Electric units							1.00		
HEATING	oil/gas units		Interior		Exterior			5.00		
APPLIANCES	Ranges		Cook Tops		Wall Ovens			2.00		
	Insta-Hot		Water heaters		Fans			2.00		
	Dryers		Disposals		Dishwasher			2.00		
	Compactors		Spa		Washing Machine			2.00		
	Others (denote)							2.00		
	MISC. (number of)	Air Cond/win	1					3.00	3.00	
		Air Cond/cent				Pools		10.00		
		HVAC		EMS		Thermostat		5.00		
	Signs						10.00			
	Alarms/res						5.00			
	Alarms/com						15.00			
	Heavy Duty(CRKT)						2.00			
	Circus/Carnv						25.00			
	Alterations						5.00			
	Fire Repairs						15.00			
	E Lights						1.00			
	E Generators						20.00			
PANELS	Service		Remote		Main			4.00		
TRANSFORMER	0-25 Kva							5.00		
	25-200 Kva							8.00		
	Over 200 Kva							10.00		
TOTAL AMOUNT DUE										
MINIMUM FEE/COMMERCIAL 35.00								MINIMUM FEE	25.00	25.00

INSPECTION: Will be ready _____ or will call _____

CONTRACTORS NAME Everything Elec **MASTER LIC. #** MC 60017606
ADDRESS 23 Bell Street Portland **LIMITED LIC. #** _____
TELEPHONE 278-5088

SIGNATURE OF CONTRACTOR Bhoda Conley



CITY OF PORTLAND

NOTICE OF VIOLATION

April 16, 2002

Edgar Beaulieu
27 Cyprus
Portland, Me 04103

RE: 27 Cyprus
CBL: (344-C-029)

Certified Mail Receipt: # 7001 1940 0004 2778 1388

Dear Mr. Beaulieu:

An evaluation of your property at 27 Cyprus Street on April 10, 2002 revealed that the structure fails to comply with Section 421. 10.8 of the BOCA 1999 Code of the City of Portland.

Attached is a list of the violations and copies of the referenced Code sections.

1. Access gate does not meet code requirements.

This is a notice of violation pursuant to Section 116.4 of the Code. All referenced violations shall be corrected within 30 days of the date of this notice. A re-inspection of the premises will occur on May 16, 2002 at which time compliance will be required. Failure to comply will result in this office referring the matter to the City of Portland Corporation Counsel for legal action and possible civil penalties, as provided for in Section 1-15 of the Code and in Title 30-A M.R.S.A. ss 4452.

This constitutes an appealable decision pursuant to Section 121.5 of the Code. Please feel free to contact me at 874-8708, if you wish to discuss the matter or have any questions.

Please be advised that the Portland City Council has amended the Building regulations to include a \$75.00 re-inspection fee. This violation will automatically cause a re-inspection at no charge. If there are any subsequent inspections, however, the \$75.00 fee will be assessed for each inspection.

Sincerely,

Kevin W. Carroll
Code Enforcement Officer
Attachments: BOCA 1999 Section 421.10.8
gg

SPECIAL USE

421.10 Enclosures for private swimming pools, spas and hot tubs: Private swimming pools, spas and hot tubs shall be enclosed in accordance with Sections 421.10.1 through 421.10.4 or by other approved barriers.

421.10.1 Outdoor private swimming pool: An outdoor private swimming pool, including an in-ground, above-ground or on-ground pool, hot tub or spa shall be provided with a barrier which shall comply with the following.

1. The top of the barrier shall be at least 48 inches (1219 mm) above finished ground level measured on the side of the barrier which faces away from the swimming pool. The maximum vertical clearance between finished ground level and the barrier shall be 2 inches (51 mm) measured on the side of the barrier which faces away from the swimming pool. Where the top of the pool structure is above finished ground level, such as an above-ground pool, the barrier shall be at finished ground level, such as the pool structure, or shall be mounted on top of the pool structure. Where the barrier is mounted on the pool structure, the opening between the top surface of the pool frame and the bottom of the barrier shall not allow passage of a 4-inch (102 mm) diameter sphere.
2. Openings in the barrier shall not allow passage of a 4-inch (102 mm) diameter sphere.
3. Solid barriers shall not contain indentations or protrusions except for normal construction tolerances and tooled masonry joints.
4. Where the barrier is composed of horizontal and vertical members and the distance between the tops of the horizontal members is less than 45 inches (1143 mm), the horizontal members shall be located on the swimming pool side of the fence. Spacing between vertical members shall not exceed $1\frac{3}{4}$ inches (44 mm) in width. Decorative cutouts shall not exceed $1\frac{3}{4}$ inches (44 mm) in width.
5. Where the barrier is composed of horizontal and vertical members and the distance between the tops of the horizontal members is 45 inches (1143 mm) or more, spacing between vertical members shall not exceed 4 inches (102 mm). Decorative cutouts shall not exceed $1\frac{3}{4}$ inches (44 mm) in width.
6. Maximum mesh size for chain link fences shall be a $1\frac{1}{4}$ -inch (32 mm) square unless the fence is provided with slats fastened at the top or the bottom which reduce the openings to not more than $1\frac{3}{4}$ inches (44 mm).
7. Where the barrier is composed of diagonal members, such as a lattice fence, the maximum opening formed by the diagonal members shall be not more than $1\frac{3}{4}$ inches (44 mm).
8. Access gates shall comply with the requirements of items 1 through 7 of Section 421.10.1, and shall be equipped to accommodate a locking device. Pedestrian access gates shall open outwards away from the pool and shall be self-closing and have a self-latching device. Gates other than pedestrian access gates shall have a self-latching device. Where the release mechanism of the self-latching device is located less than 54 inches (1372 mm) from the bottom of the gate: (a) the release mechanism shall be located on the pool side of the gate at least 3 inches (76 mm) below the top of the gate; and (b) the gate and barrier shall not have an opening greater than $\frac{1}{2}$ inch (13 mm) within 18 inches (457 mm) of the release mechanism.

9. Where a wall of a dwelling unit serves as part of the barrier and contains a door that provides direct access to the pool, one of the following shall apply:

- 9.1. All doors with direct access to the pool through that wall shall be equipped with an alarm which produces an audible warning when the door and its screen, if present, are opened. The audible warning shall commence not more than 7 seconds after the door and door screen, if present, are opened and shall sound continuously for a minimum of 30 seconds. The alarm shall have a minimum sound pressure rating of 85 dBA at 10 feet (3048 mm) and the sound of the alarm shall be distinctive from other household sounds such as smoke alarms, telephones and door bells. The alarm shall automatically reset under all conditions. The alarm shall be equipped with manual means, such as touchpads or switches, to deactivate temporarily the alarm for a single opening from either direction. Such deactivation shall last for not more than 15 seconds. The deactivation touchpads or switches shall be located at least 54 inches (1372 mm) above the threshold of the door.
 - 9.2. All doors with direct access to the pool through that wall shall be equipped with a self-closing and self-latching device with the release mechanism located a minimum of 54 inches (1372 mm) above the floor. Swinging doors shall open away from the pool area.
 - 9.3. The pool shall be equipped with a power safety cover. Where in a closed position, the cover shall be capable of holding a weight of 485 pounds (2157 N), shall not have any openings that allow passage of a $4\frac{1}{2}$ -inch (114 mm) sphere and shall incorporate a system to drain standing water that collects on the cover. The cover control switch shall be permanently installed in accordance with NFPA 70 listed in Chapter 35, and be key-operated and of a spring-loaded or momentary-contact type. Where the switch is released, the operation of the cover shall stop instantly and be capable of reversing direction immediately. The switch shall be in the line of sight of the complete pool cover.
10. Where an above-ground pool structure is used as a barrier or where the barrier is mounted on top of the pool structure, and the means of access is a fixed or removable ladder or steps, the ladder or steps shall be surrounded by a barrier which meets the requirements of items 1 through 9 of Section 421.10.1. A removable ladder shall not constitute an acceptable alternative to enclosure requirements.

Inspection Services
Michael J. Nugent
Manager

Housing & Neighborhood Services
Mark Adelson
Director



CITY OF PORTLAND

July 3, 2002

Edgar Beaulieu
27 Cypress Street
Portland, ME 04103

RE: 27 Cypress St
CBL: 344-C-029

Dear Mr. Beaulieu:

A re-inspection at the above noted property was made on June 19, 2002.

This is to certify that you have complied with our request to correct the violation(s) of the Municipal Code relating to housing conditions noted on our letter dated April 16, 2002.

This notice is intended to document that you have corrected the specific violations as previously noted. It is not intended to indicate compliance with other City regulations, it also does not imply that the structure or premises is violation free.

Thank you for your cooperation. If you have any questions, feel free to contact me at this office.

Sincerely,

A handwritten signature in cursive script that reads "Jeanie Bourke".

Jeanie Bourke
Code Enforcement Officer