

Scope of work:

The scope of work of this project includes demolition of the interior second story, constructing a dormer and new bathroom, insulating and weatherizing, where possible, and refinishing the space. The homeowner and I have visited the site with Don Mcpherson and George Froelich of the Inspections Department so they have a good idea of the project.

Window Schedule:

Egress at top of stairs – 40"x62"

4 windows in bath and sitting area Approx. - 27"x36"