

Submittal Data: 36RLXFZH

36,000 BTU Multi-Zone System

Inverter Driven Heat Pump

Job Name: CUNNINGHAM

Date: 1/17/2017

Location: 140 PENNELL AVE

Approval: \_\_\_\_\_

Engineer: \_\_\_\_\_

Construction: \_\_\_\_\_

Submitted to: \_\_\_\_\_

Unit #: \_\_\_\_\_

Submitted by: \_\_\_\_\_

Drawing #: \_\_\_\_\_

Reference: \_\_\_\_\_

### General Features

- Wired or wireless remote
- Apple catchin filter
- Ion deodorizing filter
- Auto louver: up/down
- Auto louver: 4-way
- Low ambient cooling
- Blue fin coating
- Standard Warranty: 5 years parts, 7 years compressor. Applies to systems purchased before June 1<sup>st</sup> 2015\*
- Extended Warranty: 10 years parts, 10 years compressor. Systems that have been installed on or after June 1<sup>st</sup> 2015 by licensed contractors and the online Product Registration has been submitted.\*\*
- Elite Contractor Extended Warranty: 12 years parts, 12 years compressor. Systems that have been installed on or after June 1<sup>st</sup> 2015 by contractors who have met requirements and have been approved for elite contractor status plus, the online Product Registration has been submitted.\*\*\*

### Model Information

Condenser..... AOU36RLXFZH  
Evaporator..... (ARU) / (AGU) / (AUU) / (ASU) 7 9, 12, 18, 24RLF(1)  
Connectable indoor units..... 2 - 4  
Total capacity range..... 27,000 – 39,000 Btu/h

**Electrical**..... 208/230V AC 1ph-60Hz  
Available Voltage Range..... 208/230 +/- 10%  
Minimum Circuit Ampacity..... 31.5 A  
Max Fuse Size..... 40 A

**Current**  
Starting Current..... 12.9 A  
Operating Current..... 26.0 A  
Cooling..... (non-duct) 11.9 A / (ducted) 12.9 A / (mix) 12.4 A  
Heating..... (non-duct) 11.8 A / (ducted) 12.1 A / (mix) 11.8 A

**Input Power**  
Cooling..... (non-duct) 3.52 kW / (ducted) 3.92 kW / (mix) 3.71 kW  
Heating..... (non-duct) 3.00 kW / (ducted) 3.22 kW / (mix) 3.11 kW

**Capacity**  
Nominal Cooling..... 35,200 Btu/h  
Min-Max Cooling..... 12,000 – 39,000 Btu/h  
Nominal Heating..... 36,400 Btu/h  
Min-Max Heating..... 12,000 – 42,000 Btu/h

**Compressor**..... DC Twin Rotary (inv x1)  
Motor Output..... 2,100 W  
Refrigerant..... R410a  
Pre-Charge..... 8 lbs. 13 oz.  
Oil..... RB68

**Fan Motor**  
Type: DC (condenser)..... Propeller x1  
Motor Output (condenser)..... 100 W  
Type: DC (evaporator)..... (wall-mount) Cross flow  
(compact cassette) Turbo  
(ducted) Sirocco x2 (18 k x3)  
(floor) Cross flow x2

Motor Output (Evaporator)..... (wall) 30-42W (compact cassette) 54W (ducted) 80-81W  
(floor) 16W

**Heat Exchanger**  
Dimensions (condenser)  
(H x W x D) in. (mm)..... 38-1/16 x 36-5/16 x 2-3/16 (966x922x55)  
Fin Pitch..... 1.45 FPI  
Rows x Stages..... 2 x 38  
Pipe Type (Material)..... Grooved H-Pin (Copper)  
Fin Type (Material)..... Aluminum (Blue fin)

### Operation Temperature Range

Cooling..... 14°F (-10°C) - 115°F (46°C)  
Heating..... -15°F (-26°C) - 75°F (24°C)

### Efficiency

SEER<sup>^</sup>..... 20.0 (wall-mount) 18.0 (duct) 19.0 (mix)  
EER (cooling)..... 13.0 Btu/W (wall-mount) 12.0 Btu/W(duct) 12.5 Btu/W(mix)  
COP (heating)..... 4.00 W/W (wall-mount) 3.88 W/W (duct) 3.94 W/W(mix)  
HSPF (heating)..... 10.3 (wall-mount) 9.3 (duct) 9.8 (mix)

### Enclosure (condenser)

Material..... Painted galvanized steel  
Color..... Beige (10 YR 7.5/1.0 NN)

### Sound Pressure Level

Cooling..... 53 dB(A)  
Heating..... 55 dB (A)

### Dimensions

H x W x D (condenser)  
Net in. (mm)..... 39-5/16 x 38-3/16 x 14-9/16 (998x970x370)  
Gross in. (mm)..... 45-3/4 x 45-1/4 x 18-13/16 (1,162x1,150x478)

### Connection Pipe

Liquid..... 1/4" (6.35 mm) x4  
Gas..... 3/8" (9.52 mm) x3 + 1/2" (12.70 mm) x1  
Method (Liquid/Gas)..... Brazing  
Pre-charge length (Total)..... 164 ft. (50m)  
Max length (Total)..... 230 ft. (70m)  
Max length (Each)..... 82 ft. (25m)  
Min. length (Total)..... 49 ft. (15m)  
Min length (Each)..... 16 ft. (5m)  
Max Height Difference..... 49 ft. (15m)

### Weight

Condenser..... 205 lbs. (93kg)  
Evaporators..... (wall-mount) 19 lbs. - 31 lbs.  
(compact cassette) 33 lbs.  
(ducted) 37 lbs. - 49 lbs.  
(floor) 31 lbs.

### Accessories

UTY-DMMUM..... Central wired remote control (backlit, displays room temp.)  
UTY-RNNUM..... Wired remote control  
UTY-RSNUM..... Wired remote control (simple)

### Intertek® ETL Number

AOU36RLXFZH..... 91987

\*Reference brochure for approval combinations. \*\*Test conditions are based on AHRI 210/240.  
Note: Specifications are based on the following conditions. Cooling: Indoor temperature of 80°F (26.7°C) DB/67°F (19.4°C) WB, and outdoor temperature of 95°F (35°C) DB/75°F (23.9°C) WB. Heating: Indoor temperature of 70°F (21.1°C) DB/59°F (15.°C) WB, and outdoor temperature of 47°F (8.3°C) DB/43°F (6.1°C) WB. Pipe length: 24ft. 6in. (7.5m), Height difference: 0ft. (0m) (Outdoor unit – indoor unit)  
\*\*\*Standard warranty / \*\*10 year warranty / \*\*\*12 year warranty



## Dimensions: 36RLXFZH

[Unit: in. (mm)]

