Inspections Division
Date: 11/22/17
CITY OF PORTLAND, MAINE

Scope of Framing Work

~~Overall = 397.5 sq. ft~~

Basement to ~~have~~ be finished = 475.5 approx sq. ft to be finished

Framing: 2"x4" KD with 2"x4" PT plate Ramset to floor 24" on center (non load bearing walls)

Insulation: R13 faced insulation

Drywall: Walls 1/2" sheetrock - durabond, fiber tape lightweight mud

ceiling: drop ceiling tile system

ceiling insulation: Existing R21 in ceiling joist cavities to remain

Sprinklers: Existing to be dropped below suspended ceiling.