

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



CITY OF PORTLAND BUILDING PERMIT



This is to certify that

DEUTSCHE BANK NATIONAL TRUST COMPANY

Located at

1776 WASHINGTON AVE

PERMIT ID: 2015-01530

ISSUE DATE: 08/04/2015

CBL: 352 A027001

has permission to **Add one window in the bedroom and one window in the bathroom (Second Floor) - construct a sliding door, a set of exterior stairs at the slider, and to fill in the doorway at the stairs (First Floor).**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise clsoed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

N/A

/s/ Jeanie Bourke

Fire Official

Building Official

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY
THERE IS A PENALTY FOR REMOVING THIS CARD**

Approved Property Use - Zoning

Single family

Building Inspections

Use Group: R

Type:

Single Family Dwelling

Various

MUBEC/IRC 2009

Fire Department

BUILDING PERMIT INSPECTION PROCEDURES
Please call 874-8703 (ONLY)
or email: buildinginspections@portlandmaine.gov

**Check the Status or Schedule an Inspection On-Line at
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

REQUIRED INSPECTIONS:

Framing Only

Final Inspection

Electrical Close-in

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

City of Portland, Maine - Building or Use Permit		Permit No: 2015-01530	Date Applied For: 06/26/2015	CBL: 352 A027001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
Proposed Use: Same: Single-Family Home		Proposed Project Description: Add one window in the bedroom and one window in the bathroom (Second Floor) - construct a sliding door, a set of exterior stairs at the slider, and to fill in the doorway at the stairs (First Floor).		
Dept: Zoning	Status: Approved	Reviewer: Ann Machado	Approval Date: 07/27/2015	
Note: R-3 zone min. rear - 25' - new stairs OK - section 14-425 - 4 stairs - extend 44" off building & footprint is 22 sf (stairs are 6' wide)		Ok to Issue: <input checked="" type="checkbox"/>		
Conditions:				
Dept: Building Inspecti	Status: Approved w/Conditions	Reviewer: Jeanie Bourke	Approval Date: 08/04/2015	
Note:		Ok to Issue: <input checked="" type="checkbox"/>		
Conditions:				
1) Hardwired photoelectric interconnected battery backup smoke detectors shall be installed in all sleeping rooms, protecting outside these rooms, and on every level.				
The same is required for existing buildings, where permanent wiring is feasible; or at the very least battery operated smoke detectors are required. Verification of this will be upon inspection.				
2) Window sills in locations more than 72 inches from finished grade shall be a minimum of 24 inches above the finished floor of the room, unless a window fall prevention devices is installed in accordance with section IRC Sec. R612.3 or IBC Sec. 1405.13.2.				
3) Tempered safety glazing is required at all hazardous locations per IRC 2009 Sec. R308.4 and IBC 2009 Sec. 2406.4				
4) Carbon Monoxide (CO) alarms shall be installed in each area within or giving access to sleeping rooms. That detection must be powered by the electrical service (plug-in or hardwired) in the building and battery.				
5) If there are 4 or more risers, a handrail is required on one side of stairs with ends returned if the guardrail does not meet graspability dimensions. A 2x4 is not considered graspable. One handrail is required on ramps exceed a pitch of 12:1.				
6) Connections and Fasteners to be installed per 2009 IBC Sec. 2304.9 and/or IRC Table R602.3(1)				
7) Beams & girders shall be solid or built up and bear on wood or supported by approved anchors per IBC Sec. 2308.7 and IRC R502.6				
8) This permit is approved based upon information provided by the applicant or design professional. Any deviation from the final approved plans requires separate review and approval prior to work.				