



**Boise Cascade**

Boise Structural Solutions  
20 Pomerleau Street  
Biddeford, ME 04005  
phone: 877-291-5276  
fax: 877-782-0999

TO: WALLBOARD SUPPLY  
242 RIVERSIDE STREET  
PORTLAND, ME 04103

DATE: 8/13/12

JOB #: 640109

ATTENTION: JOHN LABRIE  
REGARDING: ATTIC ACCESS

Dear John

I have reviewed the truss designs for the roof trusses supplied for the 105 Dole Street project located in Portland. Although the trusses have been installed at 16" o.c. they were originally designed to support 24" of load. Eliminating a truss for attic access would require the adjacent trusses to support 16" of load on 1 side and 8" of load on the other for a total of 24" of total load. As these were original design to support 24" of load they will perform as intended without the need for further reinforcement.

Copy to:

\_\_\_\_\_

Signed:

Normand Hord  
Design Supervisor

\_\_\_\_\_

If enclosures are not as noted, kindly notify us at once.