

FIRST FLOOR HEADER SCHEDULE INTERIOR BEARING WALLS			
MIN HEADER SIZE	MAX ROUGH OPENING	NUMBER OF JACKS	
2-2x4	1'-7"	1	
2-2x6	2'-5"	2	
2-2x8	3'-2"	2	
2-2x10	3'-10"	3	
2-2x12	4'-5"	3	
3-2x8	3'-11"	2	
3-2x10	4'-10"	2	
3-2x12	5'-7"	3	
4-2x8	3'-2"	2	
4-2×10	5'-6"	2	
4-2x12	6'-5"	2	

FIRST FLOOR HEADER SCHEDULE EXTERIOR WALLS			
MIN HEADER SIZE	MAX ROUGH OPENING	NUMBER OF JACKS	
2-2x4	2'-0"	1	
2-2x6	3'-0"	2	
2-2x8	3'.9"	2	
2-2×10	4'-7"	3	
2-2x12	5'-4"	3	
3-2x8	4'-8"	2	
3-2x10	5'-9"	2	
3-2x12	6'-8"	2	
4-2x8	3'-10"	2	
4-2x10	6'-7"	2	
4-2x12	7'-8"	2	

NOTES:

1. ALL DIMENSIONAL LUMBER FOR HEADERS SHALL BE No. SPRUCE-PINE-FIR (SPF), 19% MOISTURE CONTENT MAX, Fb=875 psi MIN.

GLENN SMITH DESIGNS
HOME PLANS AND GENERAL CONTRACTING
186 SOUTH WATERBORO RD.
LYMAN, MAINE 04002
(207) 499-2811 / CELL (207) 590-3352

THESE DRAWINGS ARE PREPARED AS A DRAFTING SERVICE ONLY. THE DRAFTER IS NOT RESPONISBLE FOR DIMENSIONAL DRAFTING OR ANY OTHER TYPE OF DESIGN AND DETAILING ERRORS.

DRAWING NO.

S3

CLIENT

KR STIFFLER CONSTRUCTION

WINDHAM, MAINE

TITLE

32 TANDBERG TRAIL
BUILDING ADDITION
2nd FLOOR FRAMING PLAN