Inspections Division
Date: 01/14/14

INTERIOR FINISH LEGEND

100213

CAPRICORN

ABBREVIATIONS

C	CARPET	T	TILE
G	GROUT	TBS	TO BE SELECTED
N/A	NOT APPLICABLE	VCB	VINYL COVE BASE
P	PAINT	VCT	VINYL COMPOSITE TILE
PL	PLASTIC LAMINATE	VSB	VINYL STRAIGHT BASE
R	RESILIENT/ RUBBER/ RUBBER TREAD	WC	WALL COVERING (VINYL/ PAPER)
SF	SQUARE FEET	WCB	WALL COVERING BORDER (VINYL/ PAPER)
SS	SOLID SURFACE/ NATURAL STONE	WD	WOOD
SYD	SQUARE YARD(S)		

CODE	MATERIAL	MANUFACTURER	PRODUCT, STYLE AND COLOR	FINISH	REMARKS/ NOTES
SV1	SHEET VINYL	MATCH EXISTING W/ HEAT WELDS	NA	NA	FLASH COVE BASE
P	PAINT	SHERWIN WILLIAMS	PRO MAR 200 ZERO VOC	TBS	
C1	CARPET	TBD	TBD		

M11 INTERIOR FINISH LEGEND

INTERIOR FINISH SCHEDULE

100213

CAPRICORN

ABBREVIATIONS

C	CARPET	SYD	SQUARE YARD(S)
G	GROUT	T	TILE
N/A	NOT APPLICABLE	TBS	TO BE SELECTED
P	PAINT	VCB	VINYL COVE BASE
PL	PLASTIC LAMINATE	VCT	VINYL COMPOSITE TILE
R	RESILIENT/ RUBBER/ RUBBER TREAD	VSB	VINYL STRAIGHT BASE
SC	SEALED CONCRETE	WC	WALL COVERING (VINYL/ PAPER)
SF	SQUARE FEET	WCB	WALL COVERING BORDER (VINYL/ PAPER)
SS	SOLID SURFACE/ NATURAL STONE	WD	WOOD

Room Information		Floor (Code order: primary / secondary or accent)		Walls (Code order: above chairrail / below chairrail)					Trim				Countertop/ Worksurface/ Cabinets		Remarks
Room #	Room Name	Floor	Grout	North Wall	East Wall	South Wall	West Wall	Wainscoting	Base	Decorative Trim(s)	Door(s)	Door & Window Moulding	Horizontal Plane	Vertical Plane	
GROUND FLOOR															
101	PEGGY	ETR	–	P	P	P	–	–	–	–	P	P	–	–	
102	WAITING	ETR	–	P	P	P	–	–	–	–	P	P	–	–	
103	OFFICE	ETR	–	P	P	–	–	–	–	–	P	P	–	–	
104	OFFICE	ETR	–	–	–	–	P	–	–	–	P	P	–	–	
105	OFFICE	ETR	–	–	–	–	–	–	–	–	–	–	–	–	
106	OFFICE	ETR	–	–	–	–	–	–	–	–	–	–	–	–	
107	ANALYTICAL RESEARCH	SV1	NA	P	P	P	P	–	SV1	–	P	P	–	–	
108	LOUNGE	ETR	–	–	–	–	–	–	–	–	–	–	–	–	
109	CORRIDOR	ETR	–	–	–	–	–	–	–	–	–	–	–	–	
110	WOMENS	ETR	–	–	–	–	–	–	–	–	–	–	–	–	
111	CONFERENCE	C1	NA	–	P	P	–	–	–	–	–	–	–	–	
112	ACCESS RR	ETR	–	–	–	–	–	–	–	–	–	–	–	–	
113	MECH	ETR	–	–	–	–	–	–	–	–	–	–	–	–	
114	WASH ROOM	REPAIR/REPLACE	–	P	–	–	–	–	–	–	–	–	–	–	REPAIR DAMAGED FLOOR OR REPLACE IF REPAIR CANNOT BE ACHIEVED
115	BUFFER #2	PATCH	–	P	–	–	–	–	–	–	–	–	–	–	PATCH IN NEW FLOOR AT NEW OPENING
116	CENTRIFUGE	ETR	–	P	–	–	P	–	–	–	–	–	–	–	PATCH HOLES IN WALL DUES TO PLUMBING REMOVAL
117	WALK-IN	ETR	–	–	–	–	–	–	–	–	–	–	–	–	
118	LAB #1	ETR	–	–	P	–	–	–	–	–	–	–	–	–	TOUCH UP WALL PAINT
119	CORRIDOR	ETR	–	–	–	–	–	–	–	–	–	–	–	–	
120	BUFFER LAB/CHEM	ETR	–	–	P	P	–	–	–	–	–	–	–	–	
121	WALK-IN	ETR	–	–	–	–	–	–	–	–	–	–	–	–	
122	CL	ETR	–	–	–	–	–	–	–	–	–	–	–	–	
123	LAB #2	ETR	–	–	P	–	–	–	–	–	–	–	–	–	
124	WALK-IN	ETR	–	–	–	–	–	–	–	–	–	–	–	–	
125	STAIR	ETR	–	–	–	–	–	–	–	–	–	–	–	–	
126	RECEIVING/SHIPPING	ETR	–	–	–	–	–	–	–	–	–	–	–	–	
MEZZANINE FLOOR PLAN															
201	OPEN OFFICE	ETR	–	P	P	P	P	–	–	–	P	P	–	–	
202	STORAGE	ETR	–	P	P	P	P	–	–	–	P	P	–	–	
203	RR	ETR	–	P	P	P	P	–	–	–	P	P	–	–	

A1 NOT USED

A11 INTERIOR FINISH SCHEDULE

PLAN NORTH

LICENSED ARCHITECT
STANLEY WALDRON GAWRON
1145
STATE OF MAINE

Gawron Turgeon
ARCHITECTS
29 Black Point Road
Scarborough, Maine 04074
www.gawronturgeon.com
207-883-4307 tel 207-883-0361 fax

CAPRICORN
OFFICE RENOVATION
12 RICE STREET . . . PORTLAND, MAINE

REVISIONS

#	DATE	DESCRIPTION
1	11.15.13	ISSUED FOR PRICING
2	11.22.13	ISSUED FOR PRICING
3	12.05.13	ISSUED FOR PRICING

DATE:	12.05.13
PROJECT #	100213
DRAWN BY:	DMR
CHECKED BY:	MT
DRAWING SCALE	AS NOTED

SHEET TITLE

INTERIOR FINISH LEGEND AND SCHEDULE

A941

© COPYRIGHT 1985-2013
REPRODUCTION OR REUSE OF THIS DOCUMENT WITHOUT WRITTEN PERMISSION OF GAWRON TURGEON ARCHITECTS IS PROHIBITED