



**DEMOLITION WORK NOTES:**

- ALL EXISTING CAT 5/5E WITHIN FACILITY SHALL BE REMOVED.
- TELCO ROOM 105 TO BE MOVED TO NEW LOCATION ON MEZZANINE. REFER TO DRAWING E2.21 FOR NEW LOCATIONS.

**GENERAL ELECTRICAL DEMOLITION NOTES**

- REFER TO DRAWINGS E1.\*\* AND E2.\*\* FOR NEW ELECTRICAL WORK.
- ELECTRICAL CONTRACTOR SHALL REMOVE AND SAFELY DISCARD ALL EXISTING ELECTRICAL OUTLETS NOTED WITH "RV". REFER TO DRAWINGS E1.\*\* AND E2.\*\* FOR MORE INFORMATION.
- PROVIDE BLANK PLATES AT ABANDONED DEVICES AND DISCONNECT OR REMOVE WIRING WHERE WALLS ARE OPEN. DE-ENERGIZE ABANDONED WIRING AT THE SOURCE TO THE DEVICE BEING REMOVED. MAINTAIN CONTINUITY TO EXISTING'S DEVICES THROUGH SPLICES WHERE DEVICES ARE REMOVED ON COMMON CIRCUITS.
- DEVICES TO BE REMOVED ARE SHOWN. CONTRACTOR IS RESPONSIBLE TO VISIT THE SITE TO MAKE THE FINAL DETERMINATION OF REMOVALS REQUIRED.
- REFER TO DRAWINGS E1.11, E1.12 AND E1.21 FOR ALL LIGHTING CHANGES, TO INCLUDE RELOCATION AND REMOVAL OF LIGHTING FIXTURES.

**REVISIONS**

NO.	DATE	DESCRIPTION