

PROPOSAL

JMAC'S Custom Concrete Inc
 P O Box 27
 Lewiston, ME 04243

Tel: (207) 784-9943
 Fax: (207) 784-9949
 Cell: (207) 212-7250
 mmccarthy@jmacscustomconcrete.com

JMC Self Storage
 980 Riverside St
 Portland, ME 04103
 Attn: Kevin Bosworth
 October 7, 2017

CONCRETE 6,400
 INSULATION 4,100

Following work to be completed at JMC Self Storage, 980 Riverside St Portland as per drawings by FLEXOSPAN drawing #'s 21667M-3A & 21667M-4A dated 10-5-17
Construction of 3,032 square feet of concrete slab – set up and install the following: form work, # 4 rebar on supports, WWF, 6 mil vapor barrier, pour, finish, & saw cut control joints. \$ 9,702.00 Installation of 2" rigid insulation (Labor Only) \$ 950.00
All Labor & Included Materials: \$ 10,652.00
Exclusions: • All excavation & backfilling by others • No concrete pumping • All access for concrete trucks by JMC Self Storage • No wet curing or sealing of new concrete slab • All ready mix concrete provided for JMC Self Storage • All elevations & building layout by JMC Self Storage • All 2" rigid insulation of be provided for by JMC Self Storage and installed by JMAC'S Custom Concrete Inc (130 – 8' x 4' sheets needed)
Terms: \$ 10,652.00 Due Upon Completion - NO RETAIN-AGE TO BE HELD

Signature (JMC Self Storage) (Kevin Bosworth)

Date

Signature (JMAC'S Custom Concrete Inc)

Date
 10-7-17

Michael T. McCarthy
 Print