

TYP. NON-RATED PARTITION DETAIL @ TOP & BOTTOM PLATES

REFERENCED FROM:

SCALE: 6" = 1'-0"

**NOT USED** 

UNUSED

REFERENCED FROM

REFERENCED FROM:


SCALE: 3/4" = 1'-0"

SCALE:  $\frac{3}{4}$  = 1'-0"

RATINGS ACOUSTIC IGS AND RATIN GENERAL PICTORIAL GENERAL WALL DESCRIPTION 3 5/8" METAL STUDS @ 16" O.C., TO UNDERSIDE OF DECK ABOVE, CONTINUOUS SOUND ATTENUATION BATTS. (1) LAYER 5/8" TYPE "X" GYPSUM WALL BOARD, FULL HEIGHT. STC = 45 3 5/8" METAL STUDS @ 16" O.C., TO UNDERSIDE OF DECK ABOVE, CONTINUOUS SOUND ATTENUATION BATTS. TAGGED SIDE: (1) LAYER 5/8" TYPE "MRX" GYPSUM WALL BOARD, FULL **OPPOSITE SIDE:** (1) LAYER 5/8" TYPE "X" GYPSUM WALL BOARD, FULL HEIGHT. 3 5/8" METAL STUDS @ 16" O.C., TO UNDERSIDE OF DECK ABOVE, CONTINUOUS SOUND ATTENUATION BATTS. (1) LAYER 5/8" TYPE "MRX" GYPSUM WALL BOARD, FULL STC = 45 3 5/8" METAL STUDS @ 16" O.C., TO 12" ABOVE CEILING, (1) LAYER 5/8" TYPE "X" GYPSUM WALL BOARD, TO 12" 3 5/8" METAL STUDS @ 16" O.C., TO UNDERSIDE OF DECK ABOVE, CONTINUOUS SOUND ATTENUATION BATTS. (1) LAYER 5/8" TYPE "X" GYPSUM WALL BOARD, FULL HEIGHT. ASSEMBLY SEALED TIGHT TO FLOOR AND UNDERSIDE OF DECK PER APPROVED UL DESIGN DETAILING. 8" METAL STUDS @ 16" O.C. FROM FINISHED FLOOR TO UNDERSIDE OF DECK ABOVE. CONTINUOUS SOUND ATTENUATION BATTS. (1) LAYER 5/8" TYPE "MRX" GWB, FULL HEIGHT. 3 5/8" METAL STUDS @ 16" O.C. FROM FINISHED FLOOR TO UNDERSIDE OF DECK ABOVE. CONTINUOUS SOUND ATTENUATION BATTS. (1) LAYER 5/8" TYPE "X" GWB, FULL HEIGHT. OPPOSITE SIDE: EXISTING WALL ASSY. TO REMAIN. INFILL TO MATCH EXISTING CONDITIONS. VERIFY EXISTING CONDITIONS. ALIGN FINISHES, BOTH SIDES OF WALL. CONDITIONS VARY THROUGHOUT FACILITY. **GENERAL PARTITION NOTES:** PROVIDE MOISTURE RESISTANT TYPE "MRX" GYPSUM WALL BOARD AT ALL WALL SURFACES WITHIN ALL TOILET

- ROOMS AND JANITOR'S CLOSET. PROVIDE TYPE "MRX" GYPSUM WALL BOARD TO 4'-0" A.F.F. BEHIND ALL SINK
- BRACE WALL ASSEMBLIES TO STRUCTURE ABOVE AT ALL DOORS AND ELSEWHERE AS REQUIRED.
- 4. PROVIDE SOLID FIRE-TREATED BLOCKING AS INDICATED ON DRAWINGS AND AS REQUIRED BY MANUFACTURER'S
- HEADS, ETC.) IN WALLS, FLOORS AND CEILINGS. UTILIZE APPROPRIATE FIRE STOPPING / SEALANT MATERIALS ONLY AT FIRE-RATED ASSEMBLIES.
- 6. SEAL ALL PENETRATIONS IN VAPOR BARRIER, (EXTERIOR WALLS, BOTTOM OF TRUSS AND CONCRETE

PARTITION SCHEDULE
REFERENCED FROM: SCALE: NTS



11-21-2017

**CWS** ARCHITECTS