



CWS ARCHITECTS
ARCHITECTURE | INTERIOR DESIGN
264 US ROUTE ONE
BOX 6, SUITE 100-2A
SCARBOROUGH, MAINE 04074
T: 207.774.4441
WWW.CWSARCH.COM

OWNER
FAIRPOINT COMMUNICATIONS

PROJECT
5 DAVIS FARM ROAD MERGER

DRAWING
UL DESIGN DETAILS

REVISIONS

DRAWING NUMBER
LS3.02

SCALE: AS NOTED
DATE: 1-2-2018

ISSUED FOR PERMITTING

System No. W-L-3065
F Ratings — 1 and 2 Hr (See Item 1)
T Rating — 0 Hr

SECTION A-A

- Wall Assembly — The 1 or 2 fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300, U400 or V400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:
 - Studs — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. (51 by 102 mm) lumber spaced 16 in. (406 mm) OC. Steel studs to be min 2-1/2 in. (64 mm) wide and spaced max 24 in. (610 mm) OC.
 - Gypsum Board* — Nom 5/8 in. (16 mm) thick gypsum board, with square or tapered edges. The gypsum board type, thickness, number of layers, fastener type and sheet orientation shall be as specified in the individual U300, U400 or V400 Series Design in the UL Fire Resistance Directory. Max diam of opening is 5-1/2 in. (138 mm) when sleeve (Item 2) is employed. Max diam of opening is 4 in. (102 mm) when sleeve (Item 2) is not employed.

The F Rating of the firestop system is equal to the fire rating of the wall assembly.

- Metallic Sleeve — (Optional) — Nom 4 in. (102 mm) diam (or smaller) steel electrical metallic tubing (EMT) or Schedule 5 (or heavier) steel pipe or nom 0.016 in. thick (0.41 mm, No. 28 galv steel sleeve installed flush with wall surfaces. The annular space between steel sleeve and periphery of opening shall be min 0 in. (0 mm, point contact) to max 1 in. (25mm). When Schedule 5 steel pipe or EMT is used, sleeve may extend up to 18 in. (457 mm) beyond the wall surface.
- Cables — Aggregate cross-sectional area of cable in opening to be max 45 percent of the cross-sectional area of the opening. The annular space between the cable bundle and the periphery of the opening to be min 0 in. (0 mm, point contact) to max 1 in. (25 mm) Cables to be rigidly supported on both sides of the wall assembly. Any combination of the following types and sizes of copper conductor cables may be used:
 - Max 7/8 No. 12 AWG with polyvinyl chloride (PVC) insulation and jacket.
 - Max 25 pair No. 24 AWG telephone cable with PVC insulation and jacket.
 - Type RG/U coaxial cable with polyethylene (PE) insulation and PVC jacket having a max outside diameter of 1/2 in. (13 mm).
 - Multiple fiber optical communication cable jacketed with PVC and having a max OD of 5/8 in. (16 mm).
 - Through Penetrating Products* — Max three copper conductor No. 8 AWG, Metal-Clad Cable*.
- AFC CABLE SYSTEMS INC
F. Max 3/C (with ground) No. 8 AWG copper conductor cable with PVC insulation and jacketing.
G. Max 3/4 in. (19 mm) diam copper ground cable with or without a PVC jacket.
H. Fire Resistant Cables* — Max 1-1/4 in. (32 mm) diam single conductor or multi conductor Type MI cable. A min 1/8 in. (3 mm) separation shall be maintained between MI cables and any other types of cable.
Through Penetrating Product* — Any cables, Metal-Clad Cable* or Armored Cable* currently Classified under the Through Penetrating Products category.
See Through Penetrating Product (XHL) category in the Fire Resistance Directory for names of manufacturers.

Hilti Firestop Systems
Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. May 31, 2007

CLASSIFIED
UL US

Page: 1 of 2

System No. W-L-1054
F Ratings — 1 and 2 Hr (See Items 1 and 3)
T Rating — 0 Hr
L Rating At Ambient — Less Than 1 CFM/Sq Ft
L Rating At 400 F — 4 CFM/Sq Ft

SECTION A-A

- Wall Assembly — The 1 or 2 hr fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300 or U400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:
 - Studs — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. lumber spaced 16 in. OC. Steel studs to be min 2-1/2 in. wide and spaced max 24 in. OC. When steel studs are used and the diam of opening exceeds the width of stud cavity, the opening shall be framed on all sides using lengths of steel stud installed between the vertical studs and screw-attached to the steel studs at each end. The framed opening in the wall shall be 4 to 6 in. wider and 4 to 6 in. higher than the diam of the penetrating item such that, when the penetrating item is installed in the opening, a 2 to 3 in. clearance is present between the penetrating item and the framing on all four sides.
 - Gypsum Board* — 5/8 in. thick, 4 ft wide with square or tapered edges. The gypsum board type, thickness, number of layers, fastener type and sheet orientation shall be as specified in the individual U300 or U400 Series Design in the UL Fire Resistance Directory. Max diam of opening is 32-1/4 in. for steel stud walls. Max diam of opening is 14-1/2 in. for wood stud walls.
The F Rating of the firestop system is equal to the fire rating of the wall assembly.

Hilti Firestop Systems
Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. December 4, 2002

CLASSIFIED
UL US

Page: 1 of 2

System No. W-L-3065
F Ratings — 1 and 2 Hr (See Item 1)
T Rating — 0 Hr

SECTION A-A

- Fill, Void or Cavity Material* — Sealant or Putty — Fill material applied within the annulus, flush with each end of the steel sleeve or wall surface. Fill material installed symmetrically on both sides of the wall. A min 5/8 in. (16 mm) thickness of sealant is required for the 1 or 2 hr F Rating. An additional 1/2 in. (13 mm) diam bead of fill material shall be applied around the perimeter of sleeve on both sides of the wall when sleeve extends beyond surface of wall.
HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — CP601S, CP606, FS-One Sealants or CP618 Putty
*Bearing the UL Classification Mark
*Bearing the UL Listing Mark

NOTE:
THESE DETAILS ARE INCLUDED FOR REFERENCE PURPOSES AND DO NOT INCLUDE ALL APPLICABLE UL SYSTEM TESTED DETAILING TO BE UTILIZED THROUGHOUT THE PROJECT. PROVIDE APPLICABLE UL SYSTEM TESTED DETAILING FOR ALL FIRE RATED AND SMOKE PARTITION PENETRATIONS, WHETHER INDICATED WITHIN THESE DRAWINGS OR NOT.

Hilti Firestop Systems
Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. May 31, 2007

CLASSIFIED
UL US

Page: 2 of 2

System No. W-J-7021
F Ratings — 1 and 2 Hr (See Item 3)
T Rating — 0 Hr
L Rating at Ambient — Less Than 1 CFM/Sq Ft
L Rating at 400 F — Less Than 1 CFM/Sq Ft

SECTION A-A

- Wall Assembly — Min 5 in. thick reinforced lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified Concrete Blocks*. Max area of opening is 1300 in. with a max dimension of 50 in.
See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.
- Steel Duct — Nom 24 in. by 48 in. (or smaller) No. 24 gauge (or heavier) galv steel duct to be installed within the firestop system. The annular space shall be min 0 (point contact) in. to a max 2 in. Duct to be rigidly supported on both sides of the wall assembly
- Firestop System — The firestop system shall consist of the following:
 - Fill, Void or Cavity Material* — Sealant — Min 5/8 in. thickness of fill material applied within annulus flush with both surfaces of wall. At point contact location, a min 1/2 in. diam bead of fill material shall be applied to the wall/duct interface on both surfaces of wall.
HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant, CP601S Elastomeric Firestop Sealant or CP606 Flexible Sealant.
 - Steel Retaining Angle — Min No. 18 MSG (0.048 in.) galv steel angles cut to fit contour of duct with a 2 in. overlap on the duct and a min 1 in. overlap on the gypsum board assembly on both surfaces of wall. 2 in. leg of angle secured to duct with min No. 8 by 3/4 in. long sheet metal screws, spaced a max of 6 in. OC.

*Bearing the UL Classification Mark

Hilti Firestop Systems
Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. August 27, 2010

CLASSIFIED
UL US

System No. W-L-2098
F Ratings — 1 and 2 Hr (See Item 1)
T Ratings — 1 and 2 Hr (see Item 1)
L Rating At Ambient — Less Than 1 CFM/Sq Ft
L Rating At 400 F — 4 CFM/Sq Ft

SECTION A-A

- Wall Assembly — The fire-rated gypsum wallboard/stud wall assembly shall be constructed of the materials and in the manner specified in the individual U300 or U400 Series Wall and Partition Designs in the UL Fire Resistance Directory and shall include the following construction features:
 - Studs — Wall framing may consist of either wood studs or steel channel studs. Wood studs to consist of nom 2 by 4 in. lumber spaced 16 in. OC. Steel studs to be min 2-1/2 in. wide and spaced max 24 in. OC.
 - Gypsum Board* — 5/8 in. thick, 4 ft wide with square or tapered edges. The gypsum wallboard type, thickness, number of layers, fastener type and sheet orientation shall be as specified in the individual Wall and Partition Design. Max diam of opening is 4-3/8 in.

The hourly F and T Ratings of the firestop system are equal to the hourly fire rating of the wall assembly in which it is installed.

- Through Penetrants — One nonmetallic pipe installed within the firestop system. Pipe to be rigidly supported on both sides of floor or wall assembly. The space between pipe and periphery of opening shall be min 3/4 in. to max 1-1/4 in. Pipe to be rigidly supported on both sides of the floor or wall assembly. The following types and sizes of nonmetallic pipes may be used:
 - Polyvinyl Chloride (PVC) Pipe — Nom 2 in. diam (or smaller) Schedule 40 PVC pipe for use in closed (process or supply) piping system.
 - Chlorinated Polyvinyl Chloride (CPVC) Pipe — Nom 2 in. diam (or smaller) SDR17 CPVC pipe for use in closed (process or supply) piping systems.
- Fill, Void or Cavity Material* — Sealant — Installed to completely fill the annular space between the pipes and gypsum wallboard on both sides of wall.
HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-One Sealant
*Bearing the UL Classification Mark

Hilti Firestop Systems
Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. January 09, 2003

CLASSIFIED
UL US

System No. W-J-1058
F Ratings — 1 and 2 Hr
T Rating — 0 Hr

SECTION A-A

- Wall Assembly — Min 5 in. thick reinforced lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified Concrete Blocks*. Max diam of opening is 13 in.
See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.
- Through Penetrants — One metallic pipe, conduit or tubing to be installed either concentrically or eccentrically within the firestop system. Pipe, conduit or tubing to be rigidly supported on both sides of the assembly. The following types and sizes of metallic pipes, conduits or tubing may be used:
 - Steel Pipe — Nom 8 in. diam (or smaller) Schedule 10 (or heavier) steel pipe.
 - Iron Pipe — Nom 8 in. diam (or smaller) cast or ductile iron pipe.
 - Conduit — Nom 4 in. diam (or smaller) steel electrical metallic tubing or steel conduit.
- Pipe Covering — Nom 2 in. thick hollow cylindrical heavy density (min 3.5 pcf) fiberglass pipe covering with an all-service jacket. Pipe covering material to extend 2 in. beyond both sides of wall surface. Longitudinal joints sealed with metal fasteners or factory-applied self-sealing (SSL) tape. The annular space between the pipe covering and periphery of opening shall be min 0 in. (point contact) to max 3/8 in.
See Pipe and Equipment Covering-Materials (BRGU) category in the Building Materials Directory for names of manufacturers. Any pipe covering material meeting the above specifications and bearing the UL Classification Marking with a Flame Spread Index of 25 or less and a Smoke Developed Index of 50 or less may be used.
- Fill, Void or Cavity Material* — Sealant — In 1 hr assemblies, min 5/8 in. thickness of fill material applied within annulus flush with both surfaces of wall. In 2 hr assemblies, min 1-1/4 in. thickness of fill material applied within annulus flush with both surfaces of wall. For both 1 and 2 hr assemblies, at point contact location between insulation and gypsum board, a min 1/2 in. bead of fill material shall be applied on both sides of wall.
HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant
*Bearing the UL Classification Mark

Hilti Firestop Systems
Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. October 22, 1998

CLASSIFIED
UL US

System No. W-J-5041

ANSI/UL1479 (ASTM E814)	CANULC S115
F Ratings — 1 and 2 Hr (See Item 1)	F Ratings — 1 and 2 Hr (See Item 1)
T Ratings — 0 and 3/4 Hr (See Item 3)	FT Ratings — 0 and 3/4 Hr (See Item 3)
L Rating At Ambient — Less Than 1 CFM/Sq Ft	FH Ratings — 1 and 2 Hr (See Item 1)
L Rating At 400 F — Less Than 1 CFM/Sq Ft	FTH Ratings — 0 and 3/4 Hr (See Item 3)
	L Rating At Ambient — Less Than 1 CFM/Sq Ft
	L Rating At 400 F — Less Than 1 CFM/Sq Ft

SECTION A-A

- Wall Assembly — Min 3-3/4 in. (95 mm) and 5 in. (127 mm) thick reinforced lightweight or normal weight (100-150 pcf or 1600-2400 kg/m³) concrete required for F and FH Ratings of 1 and 2 Hr, respectively. Wall may also be constructed of any UL Classified Concrete Blocks*. Max diam of opening is 7-1/2 in. (191 mm).
See Concrete Blocks (CAZT) category in the Fire Resistance Directory for names of manufacturers.
- Through Penetrants — One metallic pipe or tubing to be centered within the firestop system. Pipe or tubing to be rigidly supported on both sides of wall assembly. The following types and sizes of metallic pipes or tubing may be used:
 - Steel Pipe — Nom 4 in. (102 mm) diam (or smaller) Schedule 40 (or heavier) steel pipe.
 - Copper Tubing — Nom 2 in. (51 mm) diam (or smaller) Type L (or heavier) copper tubing.
 - Copper Pipe — Nom 2 in. (51 mm) diam (or smaller) regular (or heavier) copper pipe.
- Tube Insulation — Plastics* — Min 1/2 in. (13 mm) to max 3/4 in. (19 mm) thick acrylonitrile butadiene/polyvinyl chloride (AB/PVC) flexible foam furnished in the form of tubing. An annular space of min 0 in. (point contact) to max 1-1/2 in. (38 mm) is required within the firestop system. When tube insulation thickness is less than 3/4 in. (19 mm), the T, FT and FTH Ratings are 0 Hr.
See Plastics* (QMFZ2) category in the Recognized Component Directory for names of manufacturers. Any Recognized Component tube insulation material meeting the above specifications and having a UL 94 Flammability Classification of 94-5VA may be used.
- Fill, Void or Cavity Material* — Sealant — Min 5/8 in. (16 mm) thickness of fill material applied within the annulus, flush with both surfaces of wall. At the point contact location between pipe covering and wall, a min 1/2 in. (13 mm) diam bead of fill material shall be applied at the pipe covering/wall interface on both surfaces of wall.
HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC — FS-ONE Sealant
*Bearing the UL Classification Mark

Hilti Firestop Systems
Reproduced by HILTI, Inc. Courtesy of Underwriters Laboratories, Inc. February 21, 2012

CLASSIFIED
UL US