



FURNISH AND INSTALL SHUTOFF VALVE AS INDICATED. REDUCE TO 3/4"Ø AT AC UNIT AND CONNECT TO PRESS REG AT UNIT. REG FURNISHED BY AC UNIT VENDOR. (TYPICAL FOR THREE UNITS)

2"Ø FUEL GAS PIPING. RUN FROM GAS UTILITY REGULATOR OUTLET FLANGE CONN UP TO ROOF. RUN ACROSS ROOF, SPLIT AND RUN TO AC UNITS. AVOID EXISTING VENTS AND EQUIPMENT. LINEAR RUN APPROX. 180 FEET, VERTICAL RUN APPROX 30 FEET. CONFIRM IN FIELD. SEE DETAIL DRAWING FOR RISER TRAP.

NON-PENETRATING ROOF MOUNTED PIPE SUPPORT SEE DETAIL (TYPICAL)

EF-1 EXH. HOOD ON ROOF

**Roof Plan - Partial Plan**  
Scale: 3/32" = 1'-0"



Plan North

Arch Proj No. 2501
Date 24 June 08
Drawn By M.E.D.
Checked By S.H.B.

**REVISIONS**


Bunker & Savage Architects  
P.O. Box 2387  
Augusta, Maine 04338  
Tele. (207) 623-4708 Fax. (207) 623-2552  
E-Mail Address: bsarch@bunkerandsavage.com

Verizon - Construction Services  
Boston, Ma.  
125 High Street  
Verizon

**NG**  
*Neill and Gunter*  
Scarborough, Maine, U.S.A.

**ROBSONWOESE INC**  
CONSULTING ENGINEERS  
Albany Boston Buffalo Raleigh-Durham Syracuse

Verizon - Construction Services  
1 DAVIS FARM  
2nd Floor Renovation  
Portland, Maine  
ROOF PLAN

Drawing No. M2