Andersen Windows - Abbreviated Quote Report

Project Name: Littlefield-5 Wakely Parsons Pond

Quote #: 533 Print Date: 03/27/2014 Quote Date: 03/27/2014 iQ Version: 14.0

Dealer: Loranger Door & Window Co. Inc.
2325 Broadway, Suite 1
South Portland, ME. 04106-3362
(207) 772-2223 Ext. 20 Fax - (207) 773-3261
Sales Rep: Adam Loranger - aloranger@lorangerdoor.com
Created By:

Customer: Maine Properties, Inc.
Billing Address: PO Box 368
Scarborough, Maine 04074
Phone: 883-3753 Fax:
Contact: Joe Solmos
Trade ID: 730081 Promotion Code:

Item	Qty	Item Size (Operation)	Location	Unit Price	Ext. Price

0001 **1** **(CTC3)/(CXW135-2) ((F)/(L-R))** **Gable End Egress Casement Unit with Circle Top**

RO Size = 6' 0 1/2" W x 6' 7 3/4" H Unit Size = 6' 0" W x 6' 7 3/16" H

Composite Unit, White/*Pre-finished White*White - Factory Painted*, High Performance Low-E4*High Performance Low-E4 Tempered Glass, Removable Interior Grille, Mulling Location: Factory (Direct), Mull Type: Narrow Transom, Mull Priority: Horizontal
- Grille, Interior, Removable, White, Prefinished White, Renaissance, 12 Lites, 3/4", Roman Ogee , Vertical Grille Alignment to CXW135-2
- Extension Jamb, Pine and Select Hardwoods, 6 9/16", Job Site Applied, Arch/Sill
- Arch Casing, 2 1/2" Colonial Pine (Includes 2 7/8" x 2 7/8" Pine Plinth Block(s))
- Grille, Interior, Removable, White/Prefinished White, Colonial, 3W3H, 3/4", Roman Ogee
- Insect Screen, White
- Hardware Pack, PSC, Traditional Folding - White

Zone: Northern

Unit	U-Factor	SHGC	ENERGY STAR® Qualified
1	0.27	0.35	Yes
2	0.29	0.32	Yes
3	0.29	0.32	Yes

0002 **1**

RO Size = N/A **Unit Size = N/A**

FS-M04-2005 VELUX FIXED DECK
MOUNT SKYLT 30 1/16 X 37 7/8 ROUGH OPENING WITH FLASHING

Date: 05/05/14
Inspections Division
CITY OF PORTLAND MAINE