## SpectrAlert® Advance

## Selectable Output Notification Appliances



#### **Audio/Visual Devices**

#### General

System Sensor® SpectrAlert® Advance selectable-output horns, strobes and horn/strobes are rich with features guaranteed to cut installation times and maximize profits. The SpectrAlert Advance series of notification appliances is designed to simplify your installations, with features such as: plug-in designs, instant feedback messages to ensure correct installation of individual devices, and eleven field-selectable candela settings for wall and ceiling strobes and horn/strobes.

More specifically, when installing Advance products, first attach a universal mounting plate to a four-inch square, four-inch octagon, or double-gang junction box. The two-wire mounting plate attaches to a single-gang junction box.

Then, connect the notification appliance circuit wiring to the SEMS terminals on the mounting plate.

Finally, attach the horn, strobe, or horn/strobe to the mounting plate by inserting the product's tabs in the mounting plate's grooves. The device will rotate into position, locking the product's pins into the mounting plate's terminals. The device will temporarily hold in place with a catch until it is secured with a captured mounting screw.

#### SpectrAlert Advance products allow you to choose:

- 12 or 24 volts.
- At 24 volts, 15, 15/75, 30, 75, 95, 110, 115, 135, 150, 177, or 185 candela by way of a rear-mounted slide switch and front viewing window.
- · Horn tones and volume by way of a rotary switch.
- The SpectrAlert Advance series includes outdoor notification appliances. Outdoor strobes and horn/strobes (two-wire and four-wire) are available for wall or ceiling. Outdoor horns are available for wall only. All System Sensor outdoor products are rated between -40°F and 151°F (-40°C and 66°C) in wet or dry applications.

#### Models available:

- Indoor wall-mount: horn, strobe, 2-wire horn/strobe, 4-wire horn/strobe.
- Indoor ceiling-mount: strobe, 2-wire horn/strobe, 4-wire horn/strobe.
- Outdoor wall-mount: horn, strobe, 2-wire horn/strobe, 4-wire horn/strobe.
- Outdoor ceiling-mount: strobe, 2-wire horn/strobe, 4-wire horn/strobe.

#### **Features**

- Plug-in design.
- · Same mounting plate for wall- and ceiling-mount units.
- Shorting spring on mounting plate for continuity check before installation.
- · Captive mounting screw.
- · Tamper-resistance capability.
- Field-selectable candela settings on wall and ceiling units: 15, 15/75, 30, 75, 95, 110, 115, 135, 150, 177, 185.
- Automatic selection of 12 or 24 volt operation at 15 and 15/ 75 candela.
- Outdoor wall and ceiling products.



Indoor Ceiling Horn/Strobe



Outdoor Ceiling Strobe



Indoor Wall Horn/Strobe



Indoor Ceiling Strobe



Indoor Wall Horn



Outdoor Wall Strobe

- Outdoor products rated from -40°F and 151°F (-40°C and 66°C).
- Outdoor products rainproof per UL50 (NEMA 3R) and weatherproof per NEMA 4X, IP56
- Minimal intrusion into the backbox.
- Horn rated at 88+ dbA at 16 volts.
- Rotary switch for tone selection.
- · Three horn volume settings.
- · Electrically compatible with existing SpectrAlert products.

### **Engineering Specifications**

SpectrAlert Advance horns, strobes, and horn/strobes shall mount to a standard 4.0" x 4.0" x 1.5" (10.16 x 10.16 x 3.81 cm) backbox, 4.0" (10.16 cm) octagonal backbox, or a doublegang backbox. Two-wire products shall also mount to a singlegang 2.0" x 4.0" x 1.875" (5.08 x 10.16 x 4.763 cm) backbox. A universal mounting plate shall be used for mounting ceiling and wall products. The notification appliance circuit wiring shall terminate at the universal mounting plate. Also, SpectrAlert Advance products, when used with the Sync•Circuit™ Module accessory, shall be powered from a non-coded notification appliance circuit output and shall operate on a nominal 12 or 24 volts. When used with the Sync•Circuit Module, 12volt rated notification appliance circuit outputs shall operate between 9 and 17.5 volts; 24-volt rated notification appliance circuit outputs shall operate between 17 and 33 volts. Indoor SpectrAlert Advance products shall operate between 32°F and 120°F (0°C and 49°C) from a regulated DC, or full-wave-rectified, unfiltered power supply. Strobes and horn/strobes shall have field-selectable candela settings including 15, 15/75, 30, 75, 95, 110, 115, 135, 150, 177, 185.

#### **STROBE**

The strobe shall be a System Sensor SpectrAlert Advance Model \_\_\_\_\_\_ listed to UL 1971 and shall be approved for fire protective service. The strobe shall be wired as a primary-signaling notification appliance and comply with the Americans with Disabilities Act requirements for visible signaling appliances, flashing at 1 Hz over the strobe's entire operating voltage range. The strobe light shall consist of a xenon flash tube and associated lens/reflector system.

#### HORN/STROBE COMBINATION

The horn/strobe shall be a System Sensor SpectrAlert Advance Model \_\_\_\_\_\_\_ listed to UL 1971 and UL 464 and shall be approved for fire protective service. The horn/strobe shall be wired as a primary-signaling notification appliance and comply with the Americans with Disabilities Act requirements for visible signaling appliances, flashing at 1 Hz over the strobe's entire operating voltage range. The strobe light shall consist of a xenon flash tube and associated lens/reflector system. The horn shall have three audibility options and an option to switch between a Temporal 3 pattern and a Non-Temporal (continuous) pattern. These options are set by a multiple position switch. On four-wire products, the strobe shall be powered independently of the sounder. The horn on horn/strobe models shall operate on a coded or non-coded power supply.

#### **OUTDOOR PRODUCTS**

SpectrAlert Advance outdoor horns, strobes and horn/strobes shall be listed for outdoor use by UL and shall operate between -40°F and 151°F (-40°C and 66°C). The products shall be listed for use with a System Sensor outdoor/weather-proof backbox with half-inch and three-fourths-inch conduit entries.

#### SYNCHRONIZATION MODULE

The module shall be a System Sensor Sync•Circuit MDL3R or MDL3W listed to UL 464 and shall be approved for fire protective service. The module shall synchronize SpectrAlert strobes at 1 Hz and horns at Temporal 3. Also, while operating the strobes, the module shall silence the horns on horn/strobe models over a single pair of wires. The module shall mount to a 4.688" x 4.688" x 2.125" (11.906 x 11.906 x 5.398 cm) backbox. The module shall also control two Style Y (class B) circuits or one Style Z (Class A) circuit. The module shall synchronize multiple zones. Daisy-chaining two or more synchronization modules together will synchronize all the zones they control. The module shall not operate on a coded power supply.

## Strobe Current Draw, UL Maximum (mA RMS)

Candela		8 –	17.5 V	16 – 33 V		
Cana		DC	FWR	DC	FWR	
	15	123	128	66	71	
	15/75	142	148	77	81	
Standard	30	NA	N/A	94	96	
Candela	75	NA	NA	158	153	
Range	95	NA	NA	181	176	
	110	NA	NA	202	195	
	115	NA	NA	210	205	
	135	NA	NA	228	207	
High Candela	150	NA	NA	246	220	
Range	177	NA	NA	281	251	
	185	NA	NA	286	258	

#### **Operating Specifications**

- Standard operating temperature: 32°F to 120°F (0°C to 49°C).
- K Series operating temperature: -40°F to 151°F (-40°C to 66°C).
- Humidity range: 10% to 93% non-condensing (indoor products).
- · Strobe flash rate: 1 flash per second.
- Nominal voltage: regulated 12 VDC/FWR or regulated 24 VDC/FWR. NOTE: Full Wave Rectified (FWR) voltage is a non-regulated, time-varying power source that is used on some power supply and panel outputs.
- Operating voltage range: 8 V to 17.5 V (12 V nominal); or 16 V to 33 V (24 V nominal). NOTE: P, S, PC, and SC products will operate at 12 V nominal only for 15 cd and 15/75 cd.
- Input terminal wire gauge: 12 to 18 AWG (3.31 to 0.821 mm²).
- Ceiling-mount dimensions (including lens): 6.8" diameter x 2.5" deep (17.3 cm diameter x 6.4 cm deep).
- Wall-mount dimensions (including lens): 5.6" H x 4.7" W x 2.5" D (14.2 cm H x 11.9 cm W x 6.4 cm D).
- Horn dimensions: 5.6" H x 4.7" W x 1.3" D (14.2 cm H x 11.9 cm W x 3.3 cm D).

## **Agency Listings and Approvals**

The listings and approvals below apply to SpectrAlert Advance Selectable Output Notification Devices. In some cases, certain modules may not be listed by certain approval agencies, or listing may be in process. Consult factory for latest listing status

- UL Listed: S4011 (HR\_\_, HW\_\_, P2\_\_, P4\_\_, PC2\_\_, PC4\_\_ models); S5512 (models SCR, SCRH, SCW, SCWH, SR, SRH, SW, SWH); S3593 (SCRHK, SCRK, SRHK, SRK).
- ULC Listed: S4011 (HRA, HRKA); S5512 (typically "A" models, with exception of outdoor strobes). See Canadian data sheet for listings and specifications.
- FM approved
- MEA: 452-05-E
- CSFM: 7125-1653:0186 (SCR, SCRH, SCW, SCWH, SR, SRH, SW, SWH); 7300-1653:0188 (P2\_, P4\_, PC2\_, PC4\_ modules); 7135-1653:0189 (HR, HRK, HW); 7300-1653:0187 (SCRHK, SCRK, SRHK, SRK).

### Horn Current Draw, UL Maximum (mA RMS)

Sound	dB	8 –	17.5 V	16 – 33 V		
Pattern	GD	DC	FWR	DC	FWR	
Temporal	High	57	55	69	75	
Temporal	Medium	44	49	58	69	
Temporal	Low	38	44	44	48	
Non-temporal	High	57	56	69	75	
Non-temporal	Medium	42	50	60	69	
Non-temporal	Low	41	44	50	50	
Coded	High	57	55	69	75	
Coded	Medium	44	51	56	69	
Coded	Low	40	46	52	50	

## Horn and Horn/Strobe Rotary Switch Setting

Setting	Repetition Rate	dB Level
1	Temporal horn	High
2	Temporal horn	Medium
3	Temporal horn	Low
4	Normal horn	High
5	Normal horn	Medium
6	Normal horn	Low
7*	Externally coded	High
8*	Externally coded	Medium
9*	Externally coded	Low

\*NOTE: Settings 7, 8, and 9 are not available on 2-wire horn/strobe.

## Horn and Horn/Strobe Output (dBA)

Switch	Sound		8 – 1	7.5 V	16 – 33 V				
Position	Pattern	dB	DC	FW R	DC	FW R			
1	Temporal	High	78	78	84	84			
2	Temporal	Medium	74	74	80	80			
3	Temporal	Low	71	73	76	76			
4	Non-temporal	High	82	82	88	88			
5	Non-temporal	Medium	78	78	85	85			
6	Non-temporal	Low	75	75	81	81			
7*	Coded	High	82	82	88	88			
8*	Coded	Medium	78	78	85	85			
9*	Coded	Low	75	75	81	81			
*NOTE: Settings 7, 8, and 9 are not available on 2-wire horn/strobe.									


# Two-Wire Horn/Strobe, *STANDARD* Candela Range (15 – 115 cd), UL Maximum Current Draw (mA RMS)


Input, Sound Pattern, dB	8 – 17.5 V		16 – 33 V						
Level	15	15/75	15	15/75	30	75	95	110	115
DC Input, Temporal, High	137	147	79	90	107	176	194	212	218
DC Input, Temporal, Medium	132	144	69	80	97	157	182	201	210
DC Input, Temporal, Low	132	143	66	77	93	154	179	198	207
DC Input, Non-temporal, High	141	152	91	100	116	176	201	221	229
DC Input, Non-temporal, Medium	133	145	75	85	102	163	187	207	216
DC Input, Non-temporal, Low	131	144	68	79	96	156	182	201	210
FWR Input, Temporal, High	136	155	88	97	112	168	190	210	218
FWR Input, Temporal, Medium	129	152	78	88	103	160	184	202	206
FWR Input, Temporal, Low	129	151	76	86	101	160	184	194	201
FWR Input, Non-temporal, High	142	161	103	112	126	181	203	221	229
FWR Input, Non-temporal, Medium	134	155	85	95	110	166	189	208	216
FWR Input, Non-temporal, Low	132	154	80	90	105	161	184	202	211


# Two-Wire Horn/Strobe, *HIGH* Candela Range (135 – 185 cd), UL Maximum Current Draw (mA RMS)

DC Input		16 – 33 V			FWR Input	16 – 33 V			
Do input	135	150	177	185	r wix input	135	150	177	185
DC, Temporal, High	245	259	290	297	FWR, Temporal, High	215	231	258	265
DC, Temporal, Medium	235	253	288	297	FWR, Temporal, Medium	209	224	250	258
DC, Temporal, Low	232	251	282	292	FWR, Temporal, Low	207	221	248	256
DC, Non-temporal, High	255	270	303	309	FWR, Non-temporal, High	233	248	275	281
DC, Non-temporal, Medium	242	259	293	299	FWR, Non-temporal, Medium	219	232	262	267
DC, Non-temporal, Low	238	254	291	295	FWR, Non-temporal, Low	214	229	256	262

7087dim12009.tif







## **Ordering Information**

Model	Description	Model	Description			
WALL HOR	N/STROBES	CEILING HORN/STROBES				
P2R	2-wire horn/strobe, standard cd, red.	PC2R	2-wire horn/strobe, standard cd, red.			
P2RH	2-wire horn/strobe, high cd, red.	PC2RH	2-wire horn/strobe, high cd, red.			
P2RK	2-wire horn/strobe, standard cd, red, outdoor.	PC2RK	2-wire horn/strobe, standard cd, red, outdoor.			
P2RHK	2-wire horn/strobe, high cd, red, outdoor.	PC2RHK	2-wire horn/strobe, high cd, red, outdoor.			
P2W	2-wire horn/strobe, standard cd, white.	PC2W	2-wire horn/strobe, standard cd, white.			
P2WH	2-wire horn/strobe, high cd, white.	PC2WH	2-wire horn/strobe, high cd, white.			
P4R	4-wire horn/strobe, standard cd, red.	PC4R	4-wire horn/strobe, standard cd, red.			
P4RH	4-wire horn/strobe, high cd, red.	PC4RH	4-wire horn/strobe, high cd, red.			
P4RK	4-wire horn/strobe, standard cd, red, outdoor.	PC4RK	4-wire horn/strobe, standard cd, red, outdoor.			
P4RHK	4-wire horn/strobe, high cd, red, outdoor.	PC4RHK	4-wire horn/strobe, high cd, red, outdoor.			
P4W	4-wire horn/strobe, standard cd, white.	PC4W	4-wire horn/strobe, standard cd, white.			
P4WH	4-wire horn/strobe, high cd, white.	PC4WH	4-wire horn/strobe, high cd, white.			
WALL STR	OBES	CEILING STROBES				
SR	Strobe, standard cd, red.	SCR	Strobe, standard cd, red.			
SRH	Strobe, high cd, red.	SCRH	Strobe, high cd, red.			
SRK	Strobe, standard cd, red, outdoor.	SCRK	Strobe, standard cd, red, outdoor.			
SRHK	Strobe, high cd, red, outdoor.	SCRHK	Strobe, high cd, red, outdoor.			
sw	Strobe, standard cd, white.	scw	Strobe, standard cd, white.			
SWH	Strobe, high cd, white.	SCWH	Strobe, high cd, white.			
ACCESSOR	RIES	HORNS				
BBS-2A	Backbox skirt, wall, red.	HR	Horn, red.			
BBSW-2A	Backbox skirt, wall, white.	HRK	Horn, red, outdoor.			
BBSC-2A	Backbox skirt, ceiling, red.	HW	Horn, white.			
BBSCW- 2A	Backbox skirt, ceiling, white.	ACCESSORIES	, continued			
SA-WBB	Weatherproof backbox, wall.	MP-2W-20BP	2-wire indoor mounting plates, pkg of 20.			
SA-WBBC	Weatherproof backbox, ceiling. cont'd at right	MPK-2W-20BP	2-wire outdoor mounting plates, pkg of 20.			

<sup>1. &</sup>quot;High cd" refers to strobes that include 135, 150, 177, and 185 candela settings. "Standard cd" refers to strobes that include 15, 15/75, 30, 75, 95, 110, and 115 candela settings.

Sync•Circuit<sup>™</sup> is a trademark and NOTIFIER® and SpectrAlert® are registered trademarks of Honeywell International Inc. ©2010 by Honeywell International Inc. All rights reserved. Unauthorized use of this document is strictly prohibited.



This document is not intended to be used for installation purposes. We try to keep our product information up-to-date and accurate. We cannot cover all specific applications or anticipate all requirements. All specifications are subject to change without notice.

For more information, contact Notifier. Phone: (203) 484-7161, FAX: (203) 484-7118. www.notifier.com

<sup>2.</sup> For strobes and horn/strobes, add suffix "F" for French or "B" for Bilingual.

<sup>3.</sup> All outdoor models ("K" suffix) include weatherproof backbox.