NORRIS INC

PO Box 2551
2257 West Broadway
South Portland, ME 04106

1.800.370.3473
fax 207.879.0540

Reviewed for Code Compliance
Inspections Division
Approved with Conditions

Date: 10/14/13

10/4/13

Scope of Work: Lyman Moore Middle School

Norris Inc. will be installing 3 new horn strobes in the hallway outside classrooms 135- 146 and 12 new strobes inside classrooms 135-146. There is currently 1 existing horn strobe in this hallway making it difficult to hear the fire alarm when the classroom doors are closed. The school has an existing FCI panel which will remain at this time. It is a conventional (zoned) panel. The school understands that they should be thinking about an addressable upgrade, however we feel that adding notification in this area is a priority at this time. The existing panel has a current inspection sticker issued by Protection Professionals.

Norris Inc. will provide and install the additional notification devices, provide the required documentation for permits, final connections and testing according to City of Portland requirements.

Please note that we have not evaluated the rest of the building for code compliance. We are only proposing to update this particular wing at this time.

The school would like to get this work done on Columbus Day when the kids are not in school. If there is anything that can be done to push the permit through asap that would be much appreciated.