

SECTION 08381 –TRAFFIC DOORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the double action traffic doors.

1.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with Eliason Corporation for furnishing the Traffic door specified in this section. Complete installation shall be by the Contractor. For pricing quotations, placing orders, and further information, call Eliason Corporation at (800) 828-3655.

1.4 QUALITY ASSURANCE

- A. Standards: Comply with applicable industry standards.

PART 2 - PRODUCTS

2.1 TRAFFIC DOORS

- A. Easy Swing SCP-8 Double-Acting Door by Eliason Corporation.

2.2 MATERIALS

- A. Door: 3/4-inch exterior grade solid wood core with 18 gauge stainless steel edge cap and back channel; 1 inch total thickness.
 - 1. Traffic Doors to receive plastic laminate finish, (No. D315-60 Platinum by Wilsonart) both faces.

2.3 ACCESSORIES

- A. View windows 9 x 30 inch (270 sq in), clear acrylic window set in black rubber molding.

- B. ABS Scuff plates on both faces 24 inch-black.
- C. Hardware: Manufactures standard as required for installation conditions.
- D. 3 x 9 Jamb Guard.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify that openings is ready to receive work

3.2 INSTALLATION

- A. Install door unit assembly to manufacturer's installation instructions
- B. Use anchorage devices to securely fasten door assembly to door frame construction without distortion or imposed stresses.

3.3 CLEANING

- A. Remove protective material from pre-finished surfaces.
- B. Remove labels and visible markings.
- C. Wash down surfaces with a solution of mild detergent in warm water, applied with soft, clean wiping cloths. Wipe surfaces clean.

END OF SECTION 08381