

## SECTION 10100 - VISUAL DISPLAY BOARDS

## PART 1 - GENERAL

## 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

## 1.2 SUMMARY

- A. This Section includes the following:
  - 1. Bulletin board.

## 1.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with Newton Distributing Company for furnishing all the bulletin boards as specified in this section. Complete installation shall be by the Contractor. For pricing quotations, placing orders and further information call Newton Distributing Company at (877) 837-7745 or (617) 969-4002.

## 1.4 QUALITY ASSURANCE

- A. Installer Qualifications: Engage an experienced installer who is an authorized representative of the manufacturer for both installation and maintenance of the type of units required for this Project.
- B. Fire-Test-Response Characteristics: Provide bulletin boards with the following surface-burning characteristics as determined by testing assembled materials composed of facings and backings identical to those required in this Section per ASTM E 84 by a testing and inspecting agency acceptable to authorities having jurisdiction. Identify tackboards with appropriate markings of applicable testing and inspecting agency.
  - 1. Flame Spread: 25 or less.
  - 2. Smoke Developed: 10 or less.

## 1.5 WARRANTY

- A. General Warranty: Made by the Contractor under requirements of the Contract Documents.

## PART 2 - PRODUCTS

### 2.1 ACCESSORIES

- A. Metal Trim and Accessories: Fabricate frames and trim of not less than 0.062-inch-thick, extruded-aluminum alloy, size and shape as indicated, to suit type of installation. Provide straight, single-length units. Keep joints to a minimum. Miter corners to a neat, hairline closure.
  - 1. Where size of visual display boards or other conditions require support in addition to normal trim, provide structural supports or modify trim from manufacturer's standard structural support accessories to suit conditions indicated.

### 2.2 FABRICATION

- A. Assembly: Provide factory-assembled tackboard units, unless field-assembled units are required.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine wall surfaces, with Installer present, for compliance with requirements and other conditions affecting installation of visual display boards.
  - 1. Surfaces to receive bulletin board shall be dry and free of substances that would impair the bond between tackboards and substrate.
  - 2. Do not proceed with installation until unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. Deliver factory-built boards completely assembled in one piece without joints, where possible.
- B. Install units in locations as indicated on drawings and in according to manufacturer's written instructions. Keep perimeter lines straight, plumb, and level. Provide grounds, clips, backing materials, adhesives, brackets, anchors, trim, and accessories necessary for complete installation.

3.3 ADJUSTING AND CLEANING

- A. Verify that accessories required for each unit have been properly installed and that operating units function properly.
- B. Clean units according to manufacturer's written instructions.

END OF SECTION 10100

PAGE INTENTIONALLY BLANK