

SECTION 10340 – TRELIS UNIT

0.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

0.2 SUMMARY

- A. This Section includes a prefabricated trellis above the main entrance.
- B. Related Section includes the following:
 - 1. Exterior Insulation and Finish System – EIFS – Section 07240.

0.3 PREFERRED SUPPLIER

- A. CVS/Pharmacy has entered into a national account agreement with the manufacturers listed below for furnishing the trellis unit specified in this section. Complete installation shall be by the contractor. For pricing quotations, placing orders, and further information, please call the appropriate manufacturer for the area the store is located in.
 - 1. Schmidt Progressive at (800) 272-3706.
Area: CT, DC, DE, IL, IN, KY, MA, ME, MD, MI, MO, NH, NJ, NY, OH, PA, RI, TN, VA, VT, WV.
 - 2. Fibergrate Composite Structures at (508) 981-3547.
Areas: AL, GA, KS, LA, MS, MN, NC, OK, SC.

PART 2 - PRODUCTS

0.1 MANUFACTURER

- A. Subject to compliance with requirements, Provide prefabricated trellis as manufactured by Schmidt Progressive, LLC.

0.2 MATERIALS

- A. Provide trellis in profile and location as indicated on Drawings including, but not necessarily limited to, properly sized threaded tie rods and manufacturer's standard finish. Finish shall be ready for specified EIFS coat.

PART 3 - EXECUTION

0.1 INSTALLATION

- A. Install prefabricated trellis at building entrance, complete, in strict accordance with manufacturer's instructions and recommendations.

0.2 CLEANING

- A. Clean all exposed surfaces, exercising care to avoid damage to final structure and finish.

0.3 PROTECTION

- A. Initiate and maintain protection and other precautions required through the remainder of the construction period to ensure that, except for normal weathering, trellis will be free of damage or deterioration at the time of Substantial Completion.

END OF SECTION 10340