

SECTION 10425 – INTERIOR SIGNAGE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes, but is not necessarily limited to, the following types of signs:
 - 1. Graphics.
 - 2. Aisle markers.
 - 3. Toilet signs.
 - 4. Employee hand wash signs.

1.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with the manufacturers below for furnishing the interior graphics and aisle markers specified in this section. Complete installation shall be by the contractor. For pricing quotations, placing orders, and further information, please call the appropriate manufacturer for the area the store is located in.
 - 1. King Retail Solutions at (800) 533-2796, ask for the CVS Account Manager
Areas: AL, GA, IA, IL, IN, KS, KY, LA, MI, MN, MO, MS, MT, NC, ND, NE, OH, OK, SC, TN, WI, WV
 - 2. LSI Retail Graphics at (401) 766-7446, ask for the CVS Account Manager
Areas: CT, DC, DE, MA, MD, ME, NH, NJ, NY, PA, RI, VA, VT
- B. CVS/Pharmacy has entered into a national account agreement with Newton Distributing Company for furnishing the Toilet Signs and Employee Hand Wash Signs as specified in this section. Complete installation shall be by the Contractor. For pricing quotations, placing orders and further information call Newton Distributing Company at (877) 837-7745 or (617) 969-4002.

1.4 QUALITY ASSURANCE

- A. Toilet Signs:
 - 1. Signs shall comply with State and Local Codes. Refer to drawings for additional signage notes.

PART 2 - PRODUCTS

2.1 MATERIALS

A. Toilet Signs:

1. Plastic for ADA compliant raised copy and braille core plies in contrasting colors, in finishes and color combinations, as selected from the manufacturer's standards.
 - a. Signs to have 5/8-inch high letters raised 1/32-inch, accompanied by Grade 2 braille, 8" x 8" signs to have a 6-inch area for pictograms.
 - b. Famed: Plastic frame in contrasting color.
 - c. Mounting with double face tape.

B. Employee Hand Wash Signs

1. Sign is provided by owner and installed contractor

PART 3 - EXECUTION

3.1 INSTALLATION

A. Graphics and Aisle Signs:

1. Locate sign units and accessories where indicated, using mounting methods in compliance with the manufacturer's instructions and the drawings.
 - a. Install signs level, plumb, and at the height indicated or required, with sign surfaces free from distortion or other defects in appearance.
2. Wall-Mounted Panel Signs: Attach panel signs to wall surfaces using the methods as recommended by the manufacturer for the substrate encountered.

B. Toilet Signs:

1. Locate sign units and accessories where indicated, using mounting methods of the type described and in compliance with the manufacturer's instructions.
 - a. Install signs level, plumb, and at the height indicated, with sign surfaces free from distortion or other defects in appearance.
2. Wall-Mounted Panel Signs: Attach panel signs to wall surfaces using the methods indicated below:
 - a. Vinyl-Tape Mounting: Use double-sided foam tape to mount signs to smooth, nonporous surfaces. Do not use this method for vinyl-covered or rough surfaces.

C. Employee Hand Wash Signs:

1. Locate sign units and accessories where indicated, using mounting methods of the type described and in compliance with the manufacturer's instructions.
 - a. Install signs level, plumb, and at the height indicated, with sign surfaces free from distortion or other defects in appearance.
2. Wall-Mounted Panel Signs: Attach panel signs to wall surfaces using the methods indicated below:
 - a. Vinyl-Tape Mounting: Use double-sided foam tape to mount signs to smooth, nonporous surfaces. Do not use this method for vinyl-covered or rough surfaces.

3.2 CLEANING AND PROTECTION

- A. After installation, clean soiled sign surfaces according to the manufacturer's instructions. Protect units from damage until acceptance by the Owner.

END OF SECTION 10425

PAGE INTENTIONALLY BLANK