

## SECTION 10801 - TOILET ACCESSORIES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following:
  - 1. Toilet accessories.

#### 1.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with Newton Distributing Company for furnishing all the Toilet Accessories as specified in this section. Complete installation shall be by the Contractor. For pricing quotations, placing orders and further information call Newton Distributing Company at (877) 837-7745 or (617) 969-4002.

#### 1.4 QUALITY ASSURANCE

- A. Product Options: Accessory requirements, including those for materials, finishes, dimensions, capacities, and performance, are established by specific products indicated in the Toilet and Bath Accessory Schedule.
  - 1. Products of other manufacturers listed in Part 2 with equal characteristics, as judged solely by Architect, may be provided.

#### 1.5 COORDINATION

- A. Coordinate accessory locations with other work to prevent interference with clearances required for access by disabled persons, proper installation, adjustment, operation, cleaning, and servicing of accessories.
- B. Deliver inserts and anchoring devices as required to prevent delaying the Work.

#### 1.6

#### 1.7

## 1.8 WARRANTY

- A. General Warranty: Special warranty specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.
- B. Manufacturer's Mirror Warranty: Written warranty, executed by mirror manufacturer agreeing to replace mirrors that develop visible silver spoilage defects within minimum warranty period indicated.
  - 1. Minimum Warranty Period: 15 years from date of Substantial Completion.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide accessories as scheduled.

### 2.2 MATERIALS

- A. Stainless Steel: ASTM A 666, Type 304, with No. 4 finish (satin), in 0.0312-inch minimum nominal thickness, unless otherwise indicated.
- B. Galvanized Steel Sheet: ASTM A 653/A 653M, G60.
- C. Chromium Plating: ASTM B 456, Service Condition Number SC 2 (moderate service), nickel plus chromium electrodeposited on base metal.
- D. Mirror Glass: ASTM C 1036, Type I, Class 1, Quality q2, nominal 6.0 mm thick, with silvering, electroplated copper coating, and protective organic coating complying with FS DD-M-411.
- E. Galvanized Steel Mounting Devices: ASTM A 153/A 153M, hot-dip galvanized after fabrication.
- F. Fasteners: Screws, bolts, and other devices of same material as accessory unit, tamper and theft resistant when exposed, and of galvanized steel when concealed.

### 2.3 FABRICATION

- A. General: Names or labels are not permitted on exposed faces of accessories. On interior surface not exposed to view or on back surface of each accessory, provide printed, waterproof label or stamped nameplate indicating manufacturer's name and product model number.

- B. Surface-Mounted Toilet Accessories: Unless otherwise indicated, fabricate units with tight seams and joints, and exposed edges rolled. Provide concealed anchorage where possible.
- C. Framed Glass-Mirror Units: Fabricate frames for glass-mirror units to accommodate glass edge protection material. Provide mirror backing and support system that permits rigid, tamper-resistant glass installation and prevents moisture accumulation.
  - 1. Provide galvanized steel backing sheet, not less than 0.034 inch and full mirror size, with nonabsorptive filler material. Corrugated cardboard is not an acceptable filler material.
- D. Mirror-Unit Hangers: Provide mirror-unit mounting system that permits rigid, tamper- and theft-resistant installation, as follows:
  - 1. One-piece, galvanized steel, wall-hanger device with spring-action locking mechanism to hold mirror unit in position with no exposed screws or bolts.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Install accessories according to manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.
- B. Secure mirrors to walls in concealed, tamper-resistant manner with special hangers, toggle bolts, or screws. Set units level, plumb, and square at locations indicated, according to manufacturer's written instructions for substrate indicated.
- C. Install grab bars to withstand a downward load of at least 250 lbf, when tested according to method in ASTM F 446.

### 3.2 ADJUSTING AND CLEANING

- A. Adjust accessories for unencumbered, smooth operation and verify that mechanisms function properly. Replace damaged or defective items.
- B. Remove temporary labels and protective coatings.
- C. Clean and polish exposed surfaces according to manufacturer's written recommendations.

### 3.3 TOILET ACCESSORY SCHEDULE

- A. Paper Towel Dispenser: Centerpull paper towel dispenser Model #DP-QTS-180E/URO/1 IFBGF. Purchase from DelVecchio at (401) 821-2700.
- B. Toilet Tissue Dispenser: Where this designation is indicated, provide toilet tissue dispenser Model 0710 as manufactured by American Specialties, Inc.

- C. Grab Bars: Where this designation is indicated, provide stainless-steel grab bar B-6806 as manufactured by Bobrick. Size and location as shown on Drawings.
- D. Mirror Unit: Where this designation is indicated, provide mirror B-293 1836 as manufactured by Bobrick.
- E. Baby Changing Station: Where this designation is indicated, provide horizontal baby changing station Model KB 100-00 as manufactured by Koala Corporation. Purchase from Carriage Trade at (781) 933-3216.
- F. Hand Dryer: Where this designation is indicated, provide hand dryer Model XL-W as manufactured by Excel Dryer Inc. To purchase contact Lance LaFave with Newton Distributing Company at (877) 837-7745.
- G. Toilet Seat Cover Dispenser: Where this designation is indicated, provide toilet seat cover dispenser Model B-5221 as manufactured by Bobrick.
- H. Single Coat Hook: Where this designation is indicated, provide single coat hook Model 0740-Z as manufactured by American Specialties, Inc.

END OF SECTION 10801