

## SECTION 11172 – WASTE COMPACTOR

## 0.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

## 0.2 SUMMARY

- A. This Section includes waste compactor.

## 0.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with Marathon Equipment Company for furnishing the waste compactor specified in this section. Complete installation shall be by the Contractor. For pricing quotations, placing orders, and further information, please call Marathon Equipment at 800-633-8974.

## 0.4 QUALITY ASSURANCE

- A. Standards: Comply with applicable industry standards.

## 0.5 PROJECT CONDITIONS

- A. Field Measurements: Check actual location for waste compactor by accurate field measurement. Show recorded measurements on shop drawings. Coordinate fabrication schedule with construction progress to avoid delay of the work.

## PART 2 - PRODUCTS

## 0.1 WASTE COMPACTOR

- A. Provide one of the compactors below as specified on drawings.
  - 1. Model No. RJ-225NA with 40 yard compaction container, chute, magnetic switch and start/stop station.
  - 2. Model No. VIP vertical compactor with platform and compaction container.
  - 3. Model No. VIP vertical compactor with compaction container.

## 0.2 ACCESSORIES

- A. Provide accessories and features as required and as standard with the manufacturer for the Owner for the unit required.

## PART 3 - EXECUTION

### 0.1 INSPECTION

- A. Inspect installation area for a clean and level floor space; and materials for electrical wiring and connections. Compactor area shall be broom clean, free of construction debris.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 0.2 INSTALLATION

- A. Comply with manufacturer's specifications and recommendations for a complete installation.
- B. Provide proper support as standard with the manufacturer and anchor securely to surrounding construction with approved fasteners.
- C. Coordinate installation with other components of the work.
  - 1. Repair abraded areas of factory applied finishes.

### 0.3 CLEANING

- A. Clean surfaces promptly after installation. Exercise care to avoid damage to the finish. Remove excess dirt and other substances.

### 0.4 PROTECTION

- A. Initiate and maintain protection and other precautions required through the remainder of the construction period to ensure that, except for normal weathering, compactor will be free of damage or deterioration at the time of Substantial Completion.

### 0.5 DEMONSTRATION

- A. Startup Services: Engage a factory-authorized service representative to perform startup services and to train Owner's maintenance personnel as specified below:
  - 1. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
  - 2. Train Owner's maintenance personnel on procedures and schedules related to startup and shutdown, troubleshooting, servicing, and preventative maintenance.
  - 3. Review data in maintenance manuals. Refer to Division 1 Section "Closeout Procedures".

4. Schedule training with Owner, through Architect, with at least seven (7) day's advance notice.

END OF SECTION 11172

PAGE INTENTIONALLY BLANK