

## SECTION 11174 - WASTE BALERS

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. This Section includes general-purpose, commercial, waste balers.

#### 1.2 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Waste Baler Standards: Comply with ANSI Z245.5, "Safety Requirements for Baling".

#### 1.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with the manufacturers below for furnishing the waste baler as specified in this section. Complete installation shall be by the contractor. For pricing quotations, placing orders, and further information, please call the appropriate manufacturer for the area the store is located in.
  - 1. PTR Baler & Compactor Co. at (800) 523-3654 ext 2311  
Areas: Michigan only
  - 2. Ver-Teck Inc at (800) 328-3398 ext 216  
Areas: All areas except Michigan

### PART 2 - PRODUCTS

#### 2.1 Waste Baler

- A. Manufacturers: Subject to compliance with requirements, provide products by the following:
  - 1. Ver-Tech Inc.; Model M-42
  - 2. PTR Baler & Compactor Co – Model1800

## 2.2 WASTE BALER FABRICATION

- A. Fabricate baler with smooth, eased exposed edges. Fabricate bins, baler chambers, unit bodies, and similar components of steel plate with welded joints. Reinforce with structural-steel members sized and spaced to withstand impacts and pressures of normal operations and to prevent excessive long-term development of waves and valleys. Fabricate equipment with replaceable parts at points of normal wear.
- B. Provide electrical devices, controls, and materials of type and quality recommended by manufacturer for applications indicated. See Division 16 Sections for power characteristics and service to equipment, including disconnect switches.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Set waste balers level, plumb, properly aligned, and securely and accurately in place. Anchor as required for secure operation.
- B. Complete field assembly with joining methods recommended in writing by manufacturer. Grind welds smooth and restore finishes.

### 3.2 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain waste balers.

END OF SECTION 11174  
CVS CUSTOM