

SECTION 11400 – COOLER AND FREEZERS

0.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

0.2 SUMMARY

- A. This Section includes:
 - 1. Free-standing freezer.
 - 2. Pharmacy refrigerators.

0.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with MASTER -BILT for furnishing the cooler and freezers specified in this section. Complete installation shall be by the Contractor. For pricing quotations, placing orders, and further information, call MASTER-BILT at (800) 647-1284.

0.4 QUALITY ASSURANCE

- A. Standards: Comply with applicable industry standards.

0.5 PROJECT CONDITIONS

- A. Field Measurements: Check actual locations for cooler and freezers by accurate field measurement. Coordinate fabrication schedule with construction progress to avoid delay of the work.
 - 1. Where necessary, proceed with fabrication without field measurements, and coordinate fabrication tolerances to ensure proper fit.

PART 2 - PRODUCTS

0.1 COOLERS AND FREEZERS

- A. Provide prefabricated, coolers and freezers of size, profile and capacity as standard for the Owner. Standard components shall include, but not necessarily be limited to, insulation; exterior/interior finish system; doors and door hardware; shelves; electrical and refrigeration features; and condensate drainage.

0.2 ACCESSORIES

- A. Provide accessories as required and as standard with the manufacturer for the Owner for the units required.

PART 3 - EXECUTION

0.1 INSPECTION

- A. Inspect installation areas for a clean and level floor space; materials for electrical wiring and connections, and condensate drain piping shall be in place. Areas shall be broom clean, free of construction debris.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

0.2 INSTALLATION

- A. Comply with manufacturer's specifications and recommendations for a complete installation of each unit.
- B. Provide proper support for each unit as standard with the manufacturer and anchor securely to surrounding construction with approved fasteners.
- C. All penetrations through insulated panels should be sealed with both an expanding foam sealant and silicone sealant per manufacturer's requirements.
- D. Coordinate installation with other components of the work.
 - 1. Repair abraded areas of factory applied finishes.

0.3 CLEANING

- A. Clean surfaces promptly after installation. Exercise care to avoid damage to the finish. Remove excess dirt and other substances.

0.4 PROTECTION

- A. Initiate and maintain protection and other precautions required through the remainder of the construction period to ensure that, except for normal weathering, cooler and freezers are free of damage or deterioration at the time of Substantial Completion.

END OF SECTION 11400