

SECTION 12300 – STEEL GONDOLA

PART 1 - GENERAL

0.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary conditions and Division 1 Specification Sections, apply to this Section.

0.2 SUMMARY

- A. This Section includes steel gondolas.

0.3 NATIONAL ACCOUNT

- A. CVS/Pharmacy has entered into a national account agreement with Lozier Store Fixtures for furnishing the steel gondolas in this section. Complete installation shall be by the Contractor. For pricing quotations, placing orders, and further information, please call Lozier Store Fixture at (800) 228-9882.

0.4 QUALITY ASSURANCE

- A. Installer Qualifications: Engage an experienced installer who is an authorized representative of the manufacturer for installation of the type of steel gondolas walls required for this Project.

0.5 DELIVERY, STORAGE, AND HANDLING

- A. Protected materials against weather and contact with damp or wet surfaces in accordance with manufacturer's instructions and recommendations.

0.6 PROJECT CONDITIONS

- A. Field Measurements: Verify field measurements before fabrication to ensure proper fittings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
  - 1. Allow for trimming and fitting where taking field measurements before fabrication might delay the Work.
  - 2. Established Dimensions: Where field measurements cannot be made without delaying the Work, establish dimensions and proceed with fabrication without field measurements. Coordinate wall construction to ensure actual dimensions correspond to established dimensions.

## PART 2 - PRODUCTS

### 0.1 MATERIALS, GENERAL

- A. Provide panels, retainers, channel and tube style legs, metal deck, sway bars, spacers and hardware as standard with the manufacturer for the Owner for a complete installation.

## PART 3 - EXECUTION

### 0.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance. Proceed with installation only after unsatisfactory conditions have been corrected.

### 0.2 PREPARATION

- A. Clean substrates of projections and substrates detrimental to application.

### 0.3 INSTALLATION, GENERAL

- A. Do not use materials that are unsound, warped, improperly treated or finished, or too small to fabricate with proper joining arrangements.
  - 1. Do not use manufactured units with defective surfaces, sizes, or patterns.
- B. Install steel gondolas in accordance with manufacturer's instructions, level, plumb, true, and aligned with adjacent materials. Use concealed shims where necessary for alignment.
  - 1. Install steel gondolas per final merchandise plan.
  - 2. Install to tolerances as required by the manufacturer.
  - 3. Coordinate steel gondolas with materials and systems in or adjacent to it. Provide cutouts for electrical items that penetrate wall system.

### 0.4 ADJUSTING

- A. Replace visual display wall that is damaged or does not comply with requirements. Wall system may be repaired or refinished if work complies with requirements and shows no evidence of repair or refinishing. Adjust joinery for uniform appearance.

0.5 CLEANING

- A. Clean steel gondolas on exposed and semiexposed surfaces. Touch up factory-applied finishes to restore damaged or soiled areas.

END OF SECTION 12300

PAGE INTENTIONALLY BLANK