


GC: Rennovate Right Construction, LLC  
 Attn: Randy Trefethen  
 207-844-0097

Plans for construction only related to this permitted scope of work.

REAR PORCH RAILING  
 Platform finish height 22".  
 No additional changes to rear exterior entry stairs.  
 Add New Handrail at 36"



Basement Windows  
 Side D  
 (2) Vinyl Replacement Windows  
 Allside Hopper Style  
 3/4" Insulated Glass Double Locks  
 Full Screen  
 No Frame Alteration  
 Side D  
 #1: 18"x12"  
 #2: 24"x12"

DOOR SCHEDULE  
 ENTRY DOOR SPECIFICATIONS

D-1 - D2  
 Jeld-Wen 32" x 78"  
 6 Panel R-5  
 Model 38VJW166100261  
 Metal 9-Lite Door Wood Jamb  
 Replaceme Existing  
 Thermal Pane  
 No Frame Alteration

D-3 thru D-8  
 Solid Pine 6-Panel  
 Interior - Slab Only  
 30"x78"  
 Utilize Existing Jamb

16 Jackson St.  
 Portland, ME

CONSULTANTS:

REVISIONS:

PROJECT No:

DRAWN BY:

CHECKED BY:

SHEET TITLE:

SECOND FLOOR PLAN

FIRST FLOOR PLAN

JACKSON STREET

Side A