FIRE ALARM SYSTEM LAYOUT – SECOND FLOOR

SCALE: 1/8"=1'

FIRE ALARM SYSTEM LAYOUT – FIRST FLOOR

SCALE: 1/8"=1'

FIRE ALARM SYSTEM LAYOUT – GROUND LEVEL

SCALE: 1/8"=1'

DEVICE ELEVATION DETAIL

NOT TO SCALE

SYMBOL LEGEND				
QUANT.	SYM.	DESCRIPTION	MODEL	BACK BOX
1	FACP	FIRE ALARM CONTROL PANEL	FC-922	ENCLOSURE
1	MST	AES RADIO MASTER BOX		ENCLOSURE
1	ANN	FIRE ALARM ANNUNCIATOR	FT2015-R3	ENCLOSURE
2		CEILING SMOKE DETECTOR/BASE	HFP-11/DB-11	SINGLE GANG OCTOGON BO
12	CO	CEILING SMOKE/CO DETECTOR/BASE	OOHC941/DB-11	SINGLE GANG OCTOGON BO
1	135	THERMAL DETECTOR/ BASE	HFPT-11/DB-11	SINGLE GANG OCTOGON BO
59		THERMAL DETECTOR/ BASE	DT-135R	SINGLE GANG OCTOGON BO
1	200	200 DEGREE THERMAL DETECTOR/ BASE	DT-200F/HTRI-M	SINGLE GANG OCTOGON BO
6	F	MANUAL PULL STATION	MSM-KD/HTRI-M	3.5" DEEP SINGLE GANG
24	I	SINGLE INPUT MONITOR MODULE	HTRI-S	4" SQUARE E
24	H	FIRE ALARM HORN	ZH-R	4" SQUARE
12		FIRE ALARM MULTI CANDELLA HORN/STROBE	ZH-MC-R	4" SQUARE
1		FIRE ALARM MULTI CANDELLA STROBE	ZR-MC-R	4" SQUARE
1	KB	KNOX BOX		
1	WP	EXTERIOR HORN/STROBE	MTH-15-115-R-WP	
1	CELL	CELLULAR COMMUNICATOR	GS3055-ICF	ENCLOSURE

FIRE ALARM RISER DETAIL

SCALE: N.T.S.

DEVICE MOUNTING & WIRING DETAIL

SCALE: N.T.S.

Reviewed for Code Compliance Fire Prevention Division Approved with Conditions

Date: 5/7/2013

Planner: Benjamin Wallace

0 1" 2" 3"

0 8' 16' 24'

1/8"=1'-0" GRAPHIC SCALE

GENERAL NOTES	DATE	REVISIONS	REQUIRED APPROVALS
SCOPE OF WORK: INSTALL NEW ADDRESSABLE FIRE ALARM			OWNER
SYSTEM. ALL INSTALLATION PRACTICES SHALL COMPLY			
WITH NFPA 70, 72, 720.			PORTLAND FIRE DEPARTMENT
PHASE 1: REPLACE CONTROL PANEL			
PHASE 2: INSTALL NEW DEVICES			DRAWN BY CRM
NOTE: PHASE 2 TO BEGIN IMMEDIATELY FOLLOWING PHASE 1			
			CHECKED BY BWB
			CONTRACTOR LICENSE #

HUNTNGTON APTS

326 AUBURN ST.

PORTLAND, ME

CONTRACT WITH: OWNER

EASTERN FIRE SERVICES, INC.

AUBURN/LEWISTON INDUSTRIAL AIRPARK, AUBURN, MAINE 04210

FIRE ALARM SYSTI	
PLANS & DETAIL	
DWG. NO.	1 OF 1
JOB NUMBER	
SCALE	AS SHOWN
DATE	1/25/13