

DISPLAY THIS CARD ON PRINCIPAL FRONTAGE OF WORK



# CITY OF PORTLAND BUILDING PERMIT



**This is to certify that**

HAVERTY DAVID H ETALS

**Located at**

73 HAVERTYS WAY (75)

**PERMIT ID:** 2015-00336

**ISSUE DATE:** 03/31/2015

**CBL:** 384 A043001

has permission to **Build a 3 bedroom, 3 Bath, 2 Story Single Family Home with attached 784 sq ft attached garage**

provided that the person or persons, firm or corporation accepting this permit shall comply with all of the provisions of the Statues of Maine and of the Ordinances of the City of Portland regulating the construction, maintenance and use of the buildings and structures, and of the application on file in the department.

Notification of inspection and written permission procured before this building or part thereof is lathed or otherwise cloed-in. 48 HOUR NOTICE IS REQUIRED.

A final inspection must be completed by owner before this building or part thereof is occupied. If a certificate of occupancy is required, it must be procured prior to occupancy.

*/s/ David Petruccelli*

*/s/ Laurie Leader*

**Fire Official**

**Building Official**

**THIS CARD MUST BE POSTED ON THE STREET SIDE OF THE PROPERTY  
THERE IS A PENALTY FOR REMOVING THIS CARD**

*Approved Property Use - Zoning*  
Single family

*Building Inspections*

*Fire Department*

**PERMIT ID:** 2015-00336

**Located at:** 73 HAVERTYS WAY (75)

**CBL:** 384 A043001

BUILDING PERMIT INSPECTION PROCEDURES  
Please call 874-8703 (ONLY)  
or email: [buildinginspections@portlandmaine.gov](mailto:buildinginspections@portlandmaine.gov)

**Check the Status or Schedule an Inspection On-Line at  
<http://www.portlandmaine.gov/planning/permitstatus.asp>**

With the issuance of this permit, the owner, builder or their designee is required to provide adequate notice to the city of Portland Inspections Services for the following inspections. Appointments must be requested 48 to 72 hours in advance of the required inspection. The inspection date will need to be confirmed by this office.

- **Please read the conditions of approval that is attached to this permit!! Contact this office if you have any questions.**
- **Permits expire in 6 months. If the project is not started or ceases for 6 months.**
- **If the inspection requirements are not followed as stated below additional fees may be incurred due to the issuance of a "Stop Work Order" and subsequent release to continue.**
- **Per Section 107.3.1 of the Maine Uniform Building and Energy Code (MUBEC). One set of printed approved stamped construction documents shall be kept at the site of work and shall be open to inspection by building officials.**

## **REQUIRED INSPECTIONS:**

Site VISIT

Final - DRC

Setbacks and Footings Prior to Pouring

Foundation/Backfill

Close-in Plumbing/Framing

Electrical - Residential

Final - Electric

Certificate of Occupancy/Final

The project cannot move to the next phase prior to the required inspection and approval to continue, REGARDLESS OF THE NOTICE OF CIRCUMSTANCES.

IF THE PERMIT REQUIRES A CERTIFICATE OF OCCUPANCY, IT MUST BE PAID FOR AND ISSUED TO THE OWNER OR DESIGNEE BEFORE THE SPACE MAY BE OCCUPIED.

<b>City of Portland, Maine - Building or Use Permit</b>		<b>Permit No:</b> 2015-00336	<b>Date Applied For:</b> 02/23/2015	<b>CBL:</b> 384 A043001
389 Congress Street, 04101 Tel: (207) 874-8703, Fax: (207) 874-8716				
<b>Proposed Use:</b> Single Family Home		<b>Proposed Project Description:</b> Build a 3 bedroom, 3 Bath, 2 Story Single Family Home with attached 784 sq ft attached garage		
<b>Dept:</b> Zoning		<b>Status:</b> Approved w/Conditions	<b>Reviewer:</b> Ann Machado	<b>Approval Date:</b> 03/17/2015
<b>Note:</b>		<b>Ok to Issue:</b> <input checked="" type="checkbox"/>		
<b>Conditions:</b>				
<b>Dept:</b> Building Inspecti		<b>Status:</b> Approved w/Conditions	<b>Reviewer:</b> Laurie Leader	<b>Approval Date:</b> 03/31/2015
<b>Note:</b>		<b>Ok to Issue:</b> <input checked="" type="checkbox"/>		
<b>Conditions:</b>		<ol style="list-style-type: none"> <li>1) This permit is approved based upon information provided by the applicant or design professional. Any deviation from the final approved plans requires separate review and approval prior to work.</li> <li>2) Carbon Monoxide (CO) alarms shall be installed in each area within or giving access to bedrooms. That detection must be powered by the electrical service (plug-in or hardwired) in the building and battery.</li> <li>3) Energy Code compliance shall be confirmed via a ResCheck or ComCheck, <a href="http://www.energycodes.gov/software.stm#tabs-2">http://www.energycodes.gov/software.stm#tabs-2</a> certificate or alternate program standard for thermal envelope and MEP systems. This documentation is required prior to associated work for these items.</li> <li>4) Separate permits are required for any electrical, plumbing, sprinkler, fire alarm, HVAC systems, heating appliances, including pellet/wood stoves, commercial hood exhaust systems, fire suppression and fuel tanks. Separate plans may need to be submitted for approval as a part of this process.</li> <li>5) Hardwired photoelectric interconnected battery backup smoke detectors shall be installed in all bedrooms, protecting the bedrooms, and on every level.  The same is required for existing buildings, where permanent wiring is feasible; or at the very least battery operated smoke detectors are required. Verification of this will be upon inspection.</li> <li>6) The design load spec sheets for any engineered beam(s) / Trusses must be submitted to this office.</li> <li>7) When over 30" above a floor or grade, guardrail openings shall be less than 4", stairail openings shall be less than 4-3/8", and at the open side of a stair, less than 6" is allowed at the triangle of the tread/riser at the bottom rail.</li> <li>8) Tempered safety glazing is required at all hazardous locations per IRC 2009 Sec. R308.4 and IBC 2009 Sec. 2406.4</li> </ol>		
<b>Dept:</b> Fire		<b>Status:</b> Approved w/Conditions	<b>Reviewer:</b> David Petruccelli	<b>Approval Date:</b> 03/20/2015
<b>Note:</b>		<b>Ok to Issue:</b> <input checked="" type="checkbox"/>		
<b>Conditions:</b>		<ol style="list-style-type: none"> <li>1) A sprinkler system shall be installed in accordance with NFPA 13D. A no fee One- or Two-family CITY Fire Sprinkler Permit is required.</li> <li>2) A copy of the State Sprinkler permit with RMS date and signature shall be provided prior to scheduling of the final inspection.</li> <li>3) Single-station photoelectric smoke alarms are required. They shall be powered by the building's electrical service with battery backup and shall be interconnected. Smoke alarms shall be installed in the following locations: <ol style="list-style-type: none"> <li>(1) All sleeping rooms</li> <li>(2) Outside each separate sleeping area, in the immediate vicinity of the sleeping rooms</li> <li>(3) On each level of the dwelling unit, including basements.</li> </ol> </li> </ol>		

- 4) Single-station Carbon Monoxide (CO) alarms are required. They shall be powered by the building's electrical service with battery backup and shall be interconnected. CO alarms shall be installed in the following locations:
  - (1) Outside each separate dwelling unit sleeping area in the immediate vicinity of the bedrooms
  - (2) On every occupiable level of the dwelling unit, including basements, excluding attics and crawl spaces
- 5) Shall meet the requirements of 2009 NFPA 1 Fire Code.
- 6) All construction shall comply with City Code Chapter 10.
- 7) Any cutting and welding done will require a Hot Work Permit from Fire Department.

**Dept:** DRC

**Status:** Approved w/Conditions

**Reviewer:** Philip DiPierro

**Approval Date:** 03/18/2015

**Note:**

**Ok to Issue:**

**Conditions:**

- 1) A performance guarantee will be required to cover the cost of site work not completed due to seasonal conditions ie., finish grading, loaming, seeding, mulching, installation of street trees, etc. The performance guarantee must be reviewed, approved, and accepted by the Planning Authority prior to the release of a Temporary Certificate of Occupancy.
- 2) The Development Review Coordinator (874-8632) must be notified five (5) working days prior to date required for final site inspection. Please make allowances for completion of site plan requirements determined to be incomplete or defective during the inspection. This is essential as all site plan requirements must be completed and approved by the Development Review Coordinator prior to issuance of a Certificate of Occupancy. Please schedule any property closing with these requirements in mind.
- 3) All damage to sidewalk, curb, street, or public utilities shall be repaired to City of Portland standards prior to issuance of a certificate of occupancy.
- 4) A sewer permit is required for your project. Please contact Carol Merritt at 874-8300, ext . 8822. The Wastewater and Drainage section of Public Services must be notified five (5) working days prior to sewer connection to schedule an inspector for your site.
- 5) A street opening permit(s) may be required for your site. Please contact Carol Merritt at 874-8300, ext. 8822. (Only excavators licensed by the City of Portland are eligible.)
- 6) All Site work (final grading, landscaping, loam and seed) must be completed prior to issuance of a certificate of occupancy.
- 7) The Development Review Coordinator reserves the right to require additional lot grading or other drainage improvements as necessary due to field conditions.
- 8) Erosion and Sedimentation control shall be established and inspected by the Development Review Coordinator prior to soil disturbance, and shall be done in accordance with Best Management Practices, Maine Department of Environmental Protection Technical and Design Standards and Guidelines. All Erosion and Sedimentation control measures must be inspected and maintained daily.
- 9) The limits of allowable clearing shall be clearly marked with flagging or temporary fencing. Absolutely no clearing is to take place within, or encroach into the "do not disturb/no cut" zone. All conditions listed in the approved subdivision plan, as they relate to this lot shall be followed.
- 10) This project must include the installation of an individual grinder pump, backflow valve, and storage tank as part of the sewage system, in compliance with the condition of approval for the original land division approval of April 20, 2000.
- 11) This site must comply with the Landscape Preservation Standards outlined in the Land Use Ordinance, section 14-526(b)2a, stating that a minimum of 30% of existing trees, ten (10) inches DBH or greater, within the required setback, must be preserved. Trees that are designated to be saved are to be protected during excavation and construction. Tree protection fencing is to be installed around the tree canopy drip line prior to the start of any excavation. Tree protection measures are to be inspected and maintained daily.
- 12) The site shall be developed and maintained as depicted in the approved site plan, written submission of the applicant, and these written conditions of approval. The modification of the approved site plan or alteration of a parcel which was the subject of site plan approval shall require the prior approval of a revised site plan by the Planning Authority.
- 13) Two (2) City of Portland approved species and size trees must be planted on your street frontage prior to issuance of a Certificate of Occupancy.
- 14) The applicant shall have a licensed surveyor install, prior to the issuance of any Certificate of Occupancy, permanent mounumentation/pins identifying property corners.