

Second Floor Plan

Scale: 1"=10'

Total 2nd floor square footage: 1080 sq. Ft.
 Full head-height square footage: 792 sq ft.
 Sloped Sidewall Square footage: 288 sq. ft.

- ① Door size & type; see **Door Schedule**
- Ⓐ Window size, type, R.O.; see **Window Schedule**

Interior Walls: 2x4 25 ga steel studs @16" O.C. with one layer 1/2" sheetrock each side

Wet Walls: 2x6 25 ga steel studs @ 16" O.C. with one layer 1/2" sheetrock each side

Interior Load-Bearing Walls: None

NFPA 13-D sprinkler system: Refer to plan designed by Dean & Allyn, Inc. (To be submitted with sprinkler permit application)

Revisions

Date	Description
5.28.14	Added Egress Window notes per R310
5.29.14	Corrected egress window designation from type "G" to type "D"

