

ROOF FRAMING PLAN

Scale: $\frac{1}{4}$ " = 1'-0"

ROOF FRAMING NOTES:

- 1. See Structural Notes , Sheet S-1.
- 2. Built—up headers and beams shall be spiked w/ 3 rows of 16d nails

- Built—up neaders and beams shall be spiked w/ 3 rows of 16d halls @ 12" o.c.
 Provide metal hangers at all flush rafter connections.
 Provide (2) 1¾" x 9½" LVL header w/ 2" rigid insulation between over all exterior door and window openings unless noted on plan.
 See architectural drawings for wall layout and dimensions.
 Connect all Rafters to wall plate with Simpson H2.5 Seismic & Hurricane Ties per Manufacturer's Instructions..

SCALE: 1/4" = 1'-0"

1	ADDED PORCH BEAM SIZE	5/2/17
0	ISSUED FOR CONSTRUCTION	5/1/17
No.	Revision/Issue	Date

General Notes

Firm Name and Address

WOODBURY HILL PROFESSIONALS 8 WOODBURY HILL ROAD AUBURN, MAINE 04210 (207) 783-4459

Project Name and Address

Dorler Residence Morningstar Lane, Lot 3 Portland, Maine

ROOF FRAMING PLAN

DORLER