Reviewed for Code Compliance
Inspections Division
Approved with Conditions
12/03/15

Date:

exterior:
g: Clapboard, to match existing
Moisture barrier: bituthane tape around openings
Sheathing: Plywood, CDX 1/2", or equiv.
Studs: 2 x 6" @ 16" OC
Insulation: closed cell spray foam, R-35 total
Finish: 1/2" GWB
Trim: 1 x trim, TBD

Dormer, roof:
Covering: asphalt shingles,
bituthane membrane all over
Sheathing: 5/8 CDX plywood, or equiv. OSB
Insulation: closed cell spray foam, R-35
Framing: Hip rafters 2 x 6, rafters: 2x 4 @ 16" OC, as shown
Trim, exterior: duplicate exisiting

Window Schedule (Andersen or equivalent)

Andersen PN**	Q'ty	Rough Opening, w. x h.	Location	Glass area, sqft, ea.	Comments
TW3846	1	3' - 10 1/8" x 4' - 8 7/8"	Attic dormer	12.97	egress compliant, 8/8 mullions
RV2857	2	2' - 2" x 4' - 7"	Attic	2 @ 9.6	
	3 total			32.2 total	

** Specify High Performance Low-E glass = U - .28

Drawing:	Date:	Scale:
Gray Residence - Dormer Framing, South View	Dec. 6, '14	1" = 4'

Whole Home Resource 3 Tide Mill Lane, Scarborough, ME 04074 | WholeHomeResource.com | 207.883.6050