



9'-0" FIRST FLOOR CEILING HEIGHT
ENTIRE FIRST FLOOR

LEGEND

- PANEL BOX
- 110V DUPLEX RECEPTICAL
- 110V DUPLEX RECEPTICAL - SPLIT WIRED
- 220V RECEPTICAL
- WALL LIGHT
- CEILING LIGHT SURFACE MOUNTED
- RECESSED LIGHT AT CEILING
- SWITCH, SINGLE POLE
- SWITCH, THREE WAY
- SWITCH, FOUR WAY
- FAN/LIGHT FIXTURE
- RANGE/HOOD FIXTURE
- FAN/LIGHT & HEAT CEILING UNIT
- SPECIAL PURPOSE CONNECTION
- JUNCTION BOX
- AC/DC SMOKE DETECTOR
- BELL
- DOOR BELL BUTTON
- TELEPHONE OUTLET
- TELEVISION CABLE OUTLET
- THERMOSTAT
- VACUUM SYSTEM OUTLET
- CEILING FAN & LIGHT
- CEILING FAN
- SMOKE/CARBON MONOXIDE DETECTOR
- FLOOD LIGHTS

CIRCUIT DIRECTORY

NO.	AMP	WIRE	CIRCUIT	CIRCUIT	WIRE	AMP	NO.
1	40	8-4	RANGE	KIT COUNT [AFI]	12-2	20	2
3				KIT COUNT, KIT [AFI]	12-2	20	4
5	20	12-2	REFRIGERATOR	GL-KITCHEN, HALL [AFI]	14-2	15	6
7	15	14-2	GL-H.BATH, ENTRY,SD/CO[AFI]	GL-FAMILY ROOM[AFI]	14-2	15	8
9	20	12-2	DINING [AFI]	GL-BEDROOM 3, HALL [AFI]	14-2	15	10
11	15	14-2	GL-MSTR/GL BATH, CLOSET[AFI]	GL-BEDROOM 2[AFI]	14-2	15	12
13	15	14-2	GL-MSTR BDRM [AFI]	GL-FAMILY RM, EXT. GFIs[AFI]	14-2	15	14
15	20	12-2	BATH GFI's	WASHER	12-2	20	16
17	20	12-2	MICROWAVE	DRYER	10-4	30	18
19	20	12-2	DISHWASHER				20
21							22
23							24
25							26
27							28
29							30
31							32
33							34
35							36
37							38
39							40

2011 N.E.C.

- * ALL OUTLETS TO BE TAMPER RESISTANT *
- * ALL LIGHT FIXTURE BOXES TO BE HEAVY DUTY [50# MIN.] *
- * ALL EXT. GFI RECEPTACLES TO BE UV RATED *
- * MAX (2) WIRES PER HOLE THRU PLATES [WHEN CAULKED] *
- * NEUTRAL REQUIRED AT ALL LIGHTING CONTROLS *

SEE STANDARD NOTES & DETAILS DWG #8

THIRD PARTY INSPECTION AGENCY		PE / RA	
SERIAL No.	17066	REVISION	DATE
PRODUCTION No.		CHECK	DATE
HOMEOWNER: BOUCHARD/MEOLI SITE: 291 SUMMIT STREET PORTLAND, ME 04103		RICHMOND CTM-L 1st.FL ELECTRICAL PLAN	
USE GROUP: SINGLE FAMILY CONST. TYPE: VB	BUILDER: SILVER BEACH LLC DBA SILVER BEACH HOMES 83 WELWOOD RD PORTLAND ME 04103	Designer: MJG DATE: 05/05/17 SCALE: 1/4" = 1'-0" PAGE: 6A	
Westchester Modular Homes Inc 30 Reagans Mill Road, Wingdale, New York, 12594 Tel (845)832-9400 Fax (845)832-6698			