CITY OF PORTLAND MAINE
REVIEWED FOR CODE COMPLIANCE
Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: _____

NOTE: PRE-FABRICATED SILT FENCE IS ACCEPTABLE IF INSTALLED PER MANUFACTURER.

TRENCH DETAIL

LEDGE, FROZEN GROUND, HEAVY ROOTS INSTALLATION WITHOUT TRENCHING

NOTES:

1. SILT FENCE SHALL BE PLACED ON SLOPE CONTOURS TO MAXIMIZE PONDING EFFICIENCY.
2. INSPECT AND REPAIR FENCE AFTER EACH STORM EVENT AND REMOVE SEDIMENT WHEN NECESSARY. 9" (225mm) MAXIMUM RECOMMENDED STORAGE HEIGHT.
3. REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT CONTRIBUTE SEDIMENT OFF-SITE AND CAN BE PERMANENTLY STABILIZED.
4. DO NOT PLACE SILT FENCE IN STREAMS OR CONCENTRATED FLOW CONDITIONS.

SILT FENCE

FILE: SILTFENC

© 1994 JOHN McCULLAH ME DEP 2003

TYPICAL STREET TREE PLANTING

NOT TO SCALE

PLANTING SCHEDULE

QUANTITY	BOTANICAL NAME	COMMON NAME	SIZE
2 *	ACER RUBRUM 'RED SUNSET'*	RED SUNSET MAPLE*	6'-7'

*THE SPECIES OF STREET TREES SHALL BE SELECTED FROM THE CITY OF PORTLAND RECOMMENDED STREET TREE LIST (2014). TREES SELECTED FOR PLANTING SHALL VARY, MORE THAN ONE SPECIES SHALL BE PLANTED ALONG PAMELA ROAD.

STATE OF MAINE
RICHARD SCOTT BACON
No. 12048
LICENSED PROFESSIONAL ENGINEER
7-21-17

REVISIONS:	BY:	DATE:	CHANGES:

Drawing Name:

LOT #42 THE VESTA CORPORATION

Project Name and Location:

PAMELA ROAD EXTENSION

PAMELA ROAD, PORTLAND, MAINE 04101

DATE: JULY 21, 2017 | SHEET: 2 OF 2

SURVEYING ENGINEERING LAND PLANNING
Northeast Civil Solutions
INCORPORATED
381 PAYNE ROAD, SCARBOROUGH, MAINE 04074
tel 207.883.1000 fax 207.883.1001 e-mail info@northeastcivilsolutions.com

E:\LAND PROJECT\33000\33229.03 TELOS - LOT GRADING\PLANSET\33229.03- OVERALL GRADING.DWG