Reviewed for Code Compliance
Inspection Division
Department of Building Safety
Date: 07/07/16

1 BUILDING SECTION
1/4"= 1'-0"

TYPICAL ROOF CONSTRUCTION

CONTINUOUS RIDGE VENT

2x10 ROOF RAFTERS SELECT #2 OR #1 @ 16" O.C.

ROOF SHINGLES

5/8" APA RATED SHEATHING W/ 8d NAILS, RING SHANK @ 6" O.C. PANEL EDGES AND 6" O.C. INTERMEDIATE

#15 FELT PAPER

WATERPROOF MEMBRANE UP EAVES 3'

TYP. EXTERIOR WALL:
1/2" G.W.B. OVER
4 MIL. REINF. POLY VAPOR BARRIER
2x6 STUDS @ 16" O.C.
W/SOLID 2x BLOCKING AT ALL SHEATHING PANEL EDGES
7/16" APA RATED SHEATHING
8d NAILS – RING SHANK @ 4" O.C. PANEL EDGES AND 6" O.C. INTERMEDIATE (TYP.) OVER CONT. BLDG. WRAP UNDER VINYL SIDING

2 BUILDING SECTION
1/4"= 1'-0"

3 BUILDING SECTION
1/4"= 1'-0"

SECOND FLOOR FRAMING PLAN
1/4"=1'-0"

MINTE

PORTLAND, MAINE

DRAWINGS THIS SHEET
BUILDING SECTIONS
SECOND FLOOR FRAMING

05.02.16

A3