Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 07/07/16

Proposal

S.P. PLUMBING & HEATING, INC.
120 Thadeus Street, Suite 8
South Portland, Maine 04106
(207) 775-7277

PROPOSAL SUBMITTED TO	PHONE	DATE
Vesta Corp	879-2217	March 9, 2016
STREET	JOB NAME	
P.O. Box 1464	Minte House Gas Heating	
CITY, STATE AND ZIP CODE	JOB LOCATION	
Portland, Maine 04104		

Labor and materials for the installation of one forced hot water gas heating system with three zones of baseboard radiation and one zone for indirect water heater. The materials we will provide consist of:

1– Viesmann VWB1B501 Gas Boiler
1 – Lo Loss HD
1 – Super Stor 45 Water Heater
1 – ½ Feed WTR Pres Reg
1 – Extrol Hydro Exp Tank
5 – UPS 15-58FC Super Brute Pump
1 – 1 ISO Pump Flange
1 – 2 Gal Therm-X-Trol ExpTank
1 – Taco SR 504 Switching Relay
1 – Conc Vent Kit
1 – ½ Auto Air Vent
1 – Extrol Hydro Exp Tank
1 – LF ¾ Union Swt Mixing Valve
1 – ½ Feed WTR Pres Reg
120' – Sterling Kom Pac Baseboard
1 – LF ½ Vac Rel Valve
3 – Honeywell TH1100DV1000 Thermostat

Miscellaneous gas material for the installation of above heating system. Wiring and setup of boiler and controls included in price.