Reviewed for Code Compliance
Approved Subject to Review
Approved with Conditions
Date: 11/03/17

NOTE: PRE-FABRICATED SILT FENCE IS ACCEPTABLE IF INSTALLED PER MANUFACTURER.

TRENCH DETAIL

LEDGE, FROZEN GROUND, HEAVY ROOTS INSTALLATION WITHOUT TRENCHING

NOTES:

1. SILT FENCE SHALL BE PLACED ON SLOPE CONTOURS TO MAXIMIZE PONDING EFFICIENCY.
2. INSPECT AND REPAIR FENCE AFTER EACH STORM EVENT AND REMOVE SEDIMENT WHEN NECESSARY. 9" (225mm) MAXIMUM RECOMMENDED STORAGE HEIGHT.
3. REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT CONTRIBUTE SEDIMENT OFF-SITE AND CAN BE PERMANENTLY STABILIZED.
4. DO NOT PLACE SILT FENCE IN STREAMS OR CONCENTRATED FLOW CONDITIONS.

FILE: SILTFENC

SILT FENCE

© 1994 JOHN McCULLAH ME DEP 2003

TYPICAL STREET TREE PLANTING

NOT TO SCALE

PLANTING SCHEDULE			
QUANTITY	BOTANICAL NAME	COMMON NAME	SIZE
2 *	ACER RUBRUM 'RED SUNSET'*	RED SUNSET MAPLE*	6'-7'

*THE SPECIES OF STREET TREES SHALL BE SELECTED FROM THE CITY OF PORTLAND RECOMMENDED STREET TREE LIST (2014). TREES SELECTED FOR PLANTING SHALL VARY, MORE THAN ONE SPECIES SHALL BE PLANTED ALONG PAMELA ROAD.

REVISIONS:	BY:	DATE:	CHANGES:
1	SMA	9/7/17	ISSUED FOR CITY REVIEW

Drawing Name:

LOT #37 THE VESTA CORPORATION

Project Name and Location:

RESIDENTIAL GRADING PLAN

PAMELA ROAD, PORTLAND, MAINE 04101

DATE: AUGUST 7, 2017 | SHEET: 2 OF 2

STATE OF MAINE
ANTHONY P. PANCIOCCO JR.
No. 10941
LICENSED PROFESSIONAL ENGINEER
9-7-17

SURVEYING ENGINEERING LAND PLANNING
Northeast Civil Solutions
INCORPORATED
381 PAYNE ROAD, SCARBOROUGH, MAINE 04074
tel 207.883.1000 fax 207.883.1001 e-mail info@northeastcivilsolutions.com
www.northeastcivilsolutions.com

0 20' 40' 80'

E:\LAND PROJECT\33000\33229.03 TELOS - LOT GRADING\PLANSET\33229.03- OVERALL GRADING.DWG