Reviewed for Code Compliance
Inspections Division
Approved with Conditions
Date: 10/18/13

TYPICAL ROOF CONSTRUCTION

RIDGE VENT
PRE-MANUFACTURED ROOF TRUSSES @ 24" O.C.
ROOF SHINGLES
5/8" APA RATED SHEATHING W/ 8d NAILS, RING SHANK @ 6" O.C. PANEL EDGES AND 6" O.C. INTERMEDIATE
#15 FELT PAPER
WATERPROOF MEMBRANE @ EAVES.

TYP. EXTERIOR WALL:
1/2" G.W.B. OVER
4 MIL. REINF. POLY VAPOR BARRIER
2x6 STUDS @ 16" O.C.
W/SOLID 2x BLOCKING AT ALL SHEATHING PANEL EDGES
R-21 INSULATION
7/16" APA RATED SHEATHING
8d NAILS – RING SHANK @ 4" O.C. PANEL EDGES AND 6" O.C. INTERMEDIATE (TYP.) OVER CONT. BLDG. WRAP UNDER VINYL SIDING

2x10 FLOOR JOISTS W/ 3/4" T&G
APA RATED SHEATHING W/ 8d RING SHANK NAILS & CONSTRUCTION ADHESIVE (TYP.) @ 6" O.C. AT PANEL EDGES & INTERMEDIATE

1 BUILDING SECTION

1/4"= 1'-0"

GARAGE ELEVATION

1/4"= 1'-0"

RIGHT SIDE ELEVATION

1/4"= 1'-0"

TYPICAL ROOF CONSTRUCTION

RIDGE VENT
PRE-MANUFACTURED ROOF TRUSSES @ 24" O.C.
ROOF SHINGLES
5/8" APA RATED SHEATHING W/ 8d NAILS, RING SHANK @ 6" O.C. PANEL EDGES AND 6" O.C. INTERMEDIATE
#15 FELT PAPER
WATERPROOF MEMBRANE @ EAVES.

TYP. EXTERIOR WALL:
1/2" G.W.B. OVER
4 MIL. REINF. POLY VAPOR BARRIER
2x6 STUDS @ 16" O.C.
W/SOLID 2x BLOCKING AT ALL SHEATHING PANEL EDGES
R-21 INSULATION
7/16" APA RATED SHEATHING
8d NAILS – RING SHANK @ 4" O.C. PANEL EDGES AND 6" O.C. INTERMEDIATE (TYP.) OVER CONT. BLDG. WRAP UNDER VINYL SIDING

2x10 FLOOR JOISTS W/ 3/4" T&G
APA RATED SHEATHING W/ 8d RING SHANK NAILS & CONSTRUCTION ADHESIVE (TYP.) @ 6" O.C. AT PANEL EDGES & INTERMEDIATE

2 BUILDING SECTION

1/4"= 1'-0"

JOCELYNE DERASPE

PORTLAND, MAINE

DRAWINGS THIS SHEET
SECTIONS
ELEVATIONS

07/29/13

A3